

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20338-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 24-14S-13W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HOKE Well #: 1
County: RUSSELL Total Vertical Depth: 3200 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240	0	w/unknown sxs cmt
PROD	4.5	2400	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/14/2010 12:30 PM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVE FUNK Company: FUNK, DAVID A. DBA OIL AND OP Phone: (785) 483-3854

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel - 800# hulls.
Bad pipe from 240' to 800'. Did not shoot the anhydrite at 740'.
Had trouble getting logger's shot down to 1380'.
Perf: 200' - 1380'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2010 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2360' - pumped 155 sxs cement with 200# hulls.
Started displacement - had cement water to surface.
POOH. Hooked up to casing and pumped 70 sxs cement at 75# pressure.
Cement circulated out the Braden head and into cellar.
Cellar stayed full.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4260.

Plugged through: TBG
CONTROL # : 201000068001

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

RECEIVED Form CP-2/3

OCT 25 2010

KCC WICHITA

OCT 18 2010