

3 023537

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSASName & BUFFALO IV FEE FUNDAddress PLUGGING PROJECTAB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE, INC. Lic. # 30670Address: P.O. BOX 386, CAHANUTE KS. 66720Company to plug at: Hour: 8:00A.M. Day: \_\_\_\_\_ 20 Month: 7 2009Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 925' THATHAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TOCIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All ☐ Part ☒ TECHNICIANOperations Completed: Hour: 12:00P.M. Day: \_\_\_\_\_ 20 Month: 7 2009Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROMTHE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RANINTO THE 2" AND 8" ANNULUS TO 600'. CEMENT WAS PUMPED INTO THE 1" PIPEUNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1"PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 198 SACKSOF CEMENT WERE PUMPED INTO THIS WELL.Remarks: GPS NO. 9. Control # 20090003-023(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

15-205-19914-00-00

API NUMBER

15-207-02234-00-00

NE,SE,SE 1/4

Sec/Twp/Rge S4.-T.27S.-R.16E.896 feet from south section line576 feet from east section line

Lease/Well#

APT NO.9(OLE 09)

County

WOODSONWILSON

Well Total Depth

950 feet

Production Pipe:

2Size Feet 925'

Surface Casing:

8"Size Feet 40'D & A306707 20097 2009RECEIVED  
AUG 03 2009  
KCC WICHITA