

6 050296

PLUGGED

86

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-02226-000

Sec. 19, T. 11 S, R. 17W

4950 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5025

Lease Name Peavy Well # 1

Operator: Tomlinson Oil Co Inc

County Ellis 112.13

Name & Address: Box 1588

Well Total Depth 3450 feet

Great Bend, Kan

Conductor Pipe: Size _____ feet

67530

Surface Casing: Size 8 5/8 feet 150' cwc

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B & Titar Cementing Co. License Number _____

Address _____

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Star Freeman

(company name) Tomlinson Oil Co Inc. (phone) _____

were: Order 210 of 50/50 Poz mix 4% Sul 2% @ 15 sac jell & 1 sac bulls.

T.O 3450 P.B.T.O. 3418 - 8 5/8 @ 150' cwc - 5 1/2 @ 3449 1/2' w/ 125 sac

Cenky @ 1113 - Perfs 3409-15 - 3357-64 - @ V 1/2 @ 1113 w/ 600 sac cwc

Spudized salt see from 2050 to 2400'

Plugging Proposal Received by Gilbert P. Luper (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 P Day: 15 Month: July Year: 1986

ACTUAL PLUGGING REPORT Ran 3345' of 2" tubing - pulled 30 sac cement +

1 sac bulls 3415 to 3100 - Pulled 8 joints to 2695 @ 60 sac gell to 2500'

Pulled 19 joints to 2497 @ 60 sac cement to 1900' - Pulled 19 joint to 1906

and pumped 9 sac gell to 1100' Pulled 24 joints to 1150' and cemented to

slayline with 95 sac - Pulled tubing to 60' and ran to surface.

Flushed up to 8 5/8 with immediate pressure to 570 lbs. solid cement.

Remarks: Cemented by B & Titar

(If additional description necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 7-22-86

07-18-86

Signed Gilbert P. Luper (TECHNICIAN)

INV. NO. 14417

1986