

4-060545

7-11

15-051-02241-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-~~9-5-56~~

NE NE NE /4 SEC. 19, 11 S, 17 W
4950 feet from S section line
330 feet from E section line

Operator license# 9449 Lease Peavey "A" well # 1
Operator: Great Eastern Energy County Ellis

Address: 672 West 4th Street Well total depth 3608 feet
Hoisington, Kansas 67544 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 243 feet

117.26

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 10:00A.M Day: 11 Month: July Year: 94

Plugging proposal received from: Bill Reed

Company: Great Eastern Energy Phone: 316-653-2277

Were: Order 275 sxs. 60/40 posmix - 10% gel and hulls.
Plug through tubing.
Hole in casing at 2700' and tubing fish at 3579'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:45P.M., Day: 11, Month: July, Year: 94

Actual plugging report: 8 5/8" to 243'. 5 1/2" to 3606' w/75 sxs.
Squeezed at 752' and 1360'. Perf. at 1900'. Ran tubing to 3400' and
pumped 35 sxs. cement. Pulled to 1900' and pumped 70 sxs. cement.
Pulled tubing to 900' and pumped 65 sxs. cement with cement to surface.
Tied onto annulus and pumped 50 sxs. cement. Tied onto casing and
pumped 35 sxs. cement. Max. 250#. S.I.P. 200#.

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1994

CONSERVATION DIV.

Remarks: Allied Cement.

Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING X, CASING . Elevation: 2100 GL

I did / did not [] observe the plugging. Don Dutcher

(agent)

Form CP-2/3

INVOICED
JUL 20 1994
DATE
INCL. NO. 40840