

4-060863

15-051-02227-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

3-29

API Number: ~~15-0258~~

SW NE NW /4 SEC. 19, 11 S, 17 W
4290 feet from S section line
3630 feet from E section line

Operator license# 5030

Lease: Peavey Well # 2

Operator: Vess Oil Corporation

County: Ellis

Address: 8100 E. 22nd St.
North Building #300
Wichita, Kansas 67226

Well total depth 3520 114.40 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1175 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 10:00 A.M. Day: 29 Month: March Year: 1996

Plugging proposal received from: Mike Kasselmann

Company: Vess Oil Corporation Phone: 316-682-1537

Were: Order 350 sxs 60/40 posmix - 10% gel and hulls.
Well located over sloping hillside.
Casing has severe dogleg at 30' from surface.

RECEIVED
KANSAS CORPORATION
MAR 12 AM 11:11

RCMD
04-12-96

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [X], None []


Completed: Hour: 12:15 P.M. Day: 29 Month: March Year: 1996

Actual plugging report: 8 5/8" to 1175' w/500 sxs. 5 1/2" to 3520' with 100 sxs. Perfs from 3433' - 3437' - 3441' - 3449' - 3458' - 3465'. Perforated at 1200' and 575'. Tied onto production casing and pumped 315 sxs with 450# hulls. Max. P.S.I. 500#. S.I.P. 300#. Tied onto annulus and pumped 75 sxs cement with 50# hulls. Max. P.S.I. 300#. S.I.P. 150#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 1911 GL

I did/did not observe the plugging.


DH (agent)

INVOICED

DATE 4-16-96

INV. NO. 45308