

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02246-00-00
Spot: SWNE Sec/Twnshp/Rge: 19-11S-17W
4290 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: PEAVEY A TWIN Well Number: 6
County: ELLIS Total Vertical Depth: 3694 feet

Operator License No.: 9449 Conductor Pipe: Size feet: 3/20.06
Op Name: GREAT EASTERN ENERGY & DEV. COR Surface Casing: Size 8.625 feet: 1367 575 SX CMT
Address: 550 W. TEXAS STE 660 Production: Size 5.5 feet: 3693 100 SX CMT
MIDLAND, TX 79702 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/16/2002 10:00 AM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: MICHEAL DAVIGNON Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 483-2627

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 300# hulls - 20 sxs gel.
Perf 3645' to 3258' O.A. CIBP at 3637'.
Squeezed at 900' w/250 sxs and 1800' w/250 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/16/2002 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Chito's Well Service RIH with tubing to 3600'.
Allied Cementing tied onto tubing and pumped 20 sxs gel with 100# hulls,
followed with 40 sxs cement with 200# hulls mixed in.
Pulled tubing to 1400'.
Allied tied onto tubing and pumped 80 sxs to circulate cement to surface.
Pulled tubing. Allied tied onto casing with a swedge and pumped 25 sxs 60/40 pozmix with Max. P.S.I. 900#. S.I.P. 700#.
Dug out backside and did a visual check.
Backside was full of cement.
Job Completed.

RECEIVED
JAN 03 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY - TICKET #11524.

Plugged through: TBG

District: 04

Signed Pat Staab

(TECHNICIAN)

INVOICED
DATE 1-6-03
WEL. NO. 2003061035

Form CP-2/3

DEC 30 2002

MURFIN DRILLING COMPANY

#6 PEAVEY 'A' (TWIN)

19-11-17W
SW NE NE

Contr. MURFIN DRLG CO

ELLIS County

E 2104KB Comm. 2-7-58

Comp. 5-9-58

IP

25 BOPD

Tops	Depth	Datum
ANH	1353	751
TOP	3041	-937
HEEB	3270	-1166
LANS	3315	-1211
ARB	3590	-1486
TD	3694	-1590

Casing

8" 1367

5" 3693

PERF 3645-49: 3655-59: TST 70
BFPH, 10% WTR: FU 2618' FLD;
2210' OIL, 408' WTR

BEMIS SHUTTS POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS