

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-01354-00-00
Spot: SWNENE Sec/Twnshp/Rge: 19-11S-17W
990 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: PEAVEY A Well Number: 2
County: ELLIS Total Vertical Depth: 3598 feet

Operator License No.: 9449 Conductor Pipe: Size feet: 3 1/2
Op Name: GREAT EASTERN ENERGY & DEV. CORP Surface Casing: Size 8.625 feet: 383 225 sx
Address: 500 W. TEXAS STE 955 Production: Size 5.5 feet: 3596 100 sx
MIDLAND, TX 79702 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/12/2002 12:30 PM
Plug Co. License No.: 9449 Plug Co. Name: GREAT EASTERN ENERGY & DEV. CORP.
Proposal Rcvd. from: MIKE DAVIGNON Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 600# hulls - 15 sxs gel spacer.
Perfs 3349' - 3477'.
PBTD 3608'.
Fluid 300' from surface.
Run tubing to plug.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/12/2002 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Chito's Well Service ran tubing to 3300' with bit on bottom.
Washed down 16 joints mud - circulated clean.
Unable to reach old T.D. of 3608'.
Allied pumped 10 sxs gel spacer, followed with 25 sxs 60/40 pozmix - 10% gel.
Pulled tubing to 1500'.
Allied pumped 140 sxs cement - circulated.
PTOH.
Allied squeezed with 55 sxs. Max. P.S.I. 400#. S.I.P. 0#.
Hooked up to 8 5/8" and pumped 30 sxs. S.I.P. 0#. Hole full.
(Note: Plugged casing thru bit - no hulls used.)

RECEIVED
APR 25 2002
4-25-02
KCC TECHNICIAN

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-26-02

WV. NO. 2002061708

APR 23 2002

MURFIN DRILLING

#2 PEAVEY 'A'

19-11-17W
SW NE NE

Contr. MURFIN DRLG

ELLIS County

E 2104RB Comm. 1-11-57 IP 250 BOPD

Tops	Depth	Datum
ANH	1353	751
LANS	3315	-1211
ARB	3595	-1191
TD	3598	-1191

Casing

8" 380

5" 3596

DST 3390-3406/30", 3' MUD,
BHP 350#

DST 3411-18/1 HR, 240' O,
180' WTRY O, 75' WTR, BHP
1080#

DST 3470-90/1 HR, 500' O &
BURNETT MCO, BHP 1000#

TST 65 BOPH,
1500' OB

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

11-10-57