

4-30

6-050109

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-05503-00-00

NW SE NW /4 SEC. 20, 11 S, 17 W
3630 feet from S section line
3630 feet from E section line

Operator license# 5992 Lease Hadley well # A-5

Operator: Patton Oil Co. County Ellis

Address: 672 West 4th Well total depth 3543 feet ^{115.14}
Hoisington, Kansas 67544 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 1146 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso License# 6050

Address: P. O. Box 347, Chase, Kansas

Company to plug at: Hour: PM Day: 30 Month: April Year: 1993

Plugging proposal received from: Darrell Kelso

Company: Kelso phone: 316-938-2943

Were: Shoot casing below salt section, pull to base, spot plug. Pull to Anhydrite, spot plug. Pull out of plug and circulate cement to surface. Pull remaining casing and fill to surface. Order 210 sx
60/40 poz, 10% gel. RECEIVED KANSAS CORPORATION COMMISSION

Elevation: 1894' TD: 3543' PBD: 3429' Perfs: 3410'-3418'
Anhydrite base 1140' Base Salt Section 1850' MAY 12 1993
8 5/8" at 1146' with 500 sx 5 1/2" at 3499' with 100 sx

Plugging Proposal Received by: Dennis Hamel CONSERVATION DIVISION WICHITA, KS
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 2:15 PM, Day: 30, Month: April, Year: 1993

Actual plugging report: Shot casing at 2000'. Pulled to 1900', pumped 35 sx 60/40 poz, 8% gel. Pulled casing to 1200', pumped 25 sx 60/40 poz, 8% gel. Pulled casing to 650', pumped 100 sx 60/40 poz, 8% gel. Pulled casing to 220' pumped 40 sx 60/40 poz, 8% gel, circ cement. Pulled remaining casing. Topped off with 10 sx 60/40 poz, 8% gel. Plug down at 2:15 PM

Remarks: Allied cementing on location
Condition of casing(in hole): GOOD Good BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X NO
Plugged through TUBING , CASING X Elevation: 1894 GL

I did [XX] / did not [] observe the plugging.

Bruce D. Basye
Bruce D. Basye
OK (agent)

INVOICED
DATE 5-14-93
INV. NO. 37695