

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

11-20-08

Operator: License # 32920

Name: W.R. Williams, Inc.

Address: P.O. Box 15163

City/State/Zip: Amarillo, Texas 79105

Purchaser: Duke Energy

Operator Contact Person: Rob Williams

Phone: (806) 374-4555

Contractor: Name: Trinidad Drilling, LP

License: 33784

Wellsite Geologist: _____

Designate Type of Completion:

New Well Re-Entry Workover

Oil SWD SIOW Temp. Abd.

Gas ENHR SIGW

Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____

Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____

Deepening Re-perf. Conv. to Enhr./SWD

Plug Back Plug Back Total Depth

Commingled Docket No. _____

Dual Completion Docket No. _____

Other (SWD or Enhr.?) Docket No. _____

09-07-2008 09-09-2008 09-29-2008

Spud Date or 09-07-2008 Date Reached TD 09-09-2008 Completion Date or 09-29-2008 Recompletion Date

API No. 15 - 075-20840-00-00

County: Hamilton

 - - C - SE Sec. 4 Twp. 22 S. R. 40 East West

1320 feet from (S) / N (circle one) Line of Section

1320 feet from (E) / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE (SE) NW SW

Lease Name: Prickett Well #: 2

Field Name: Bradshaw

Producing Formation: Upper Winfield

Elevation: Ground: 3549 Kelly Bushing: 3555

Total Depth: 2764 Plug Back Total Depth: 2756

Amount of Surface Pipe Set and Cemented at 263 KB, 257 GL Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from 2762

feet depth to Surface w/ 500 sx cmt.

Drilling Fluid Management Plan AH II ncr 1-6-09

(Data must be collected from the Reserve Pit)

Chloride content 15,000 ppm Fluid volume 900 bbls

Dewatering method used Evaporation

Location of fluid disposal if hauled offsite: _____

Operator Name: _____

Lease Name: _____ License No.: _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West

County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Rob Williams

Title: President Date: November 20, 2008

Subscribed and sworn to before me this 20th day of November

20 08
Notary Public: Linda K. McKean



KCC Office Use ONLY

Letter of Confidentiality Received

If Denied, Yes Date: _____

Wireline Log Received

Geologist Report Received

UIC Distribution

Operator Name: W.R. Williams, Inc. Lease Name: Prickett Well #: 2
 Sec. 4 Twp. 22 S. R. 40 East West County: Hamilton

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

Compensated Density Neutron

CONFIDENTIAL

Log Formation (Top), Depth and Datum Sample

| Name | Top | Datum |
|-------------------|------|--------|
| Base Stone Corral | 2285 | + 1270 |
| Chase Group | 2665 | + 890 |

RECEIVED
 KANSAS CORPORATION COMMISSION
NOV 24 2008
 CONSERVATION DIVISION
 WICHITA, KS

| CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used | | | | | | | |
|---|-------------------|---------------------------|-------------------|---------------|----------------|--------------|----------------------------|
| Report all strings set-conductor, surface, intermediate, production, etc. | | | | | | | |
| Purpose of String | Size Hole Drilled | Size Casing Set (In O.D.) | Weight Lbs. / Ft. | Setting Depth | Type of Cement | # Sacks Used | Type and Percent Additives |
| Surface | 12-1/4 | 8-5/8 | 23 | 263 | Common | 185 | 3% cc, 2% gel |
| Production | 7-7/8 | 4-1/2 | 10.5 | 2762 | Lite, C | 625 | 1/4# floeal, 5# gilsonite |

| ADDITIONAL CEMENTING / SQUEEZE RECORD | | | | |
|--|------------------|----------------|-------------|----------------------------|
| Purpose: | Depth Top Bottom | Type of Cement | #Sacks Used | Type and Percent Additives |
| <input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone | | | | |

| Shots Per Foot | PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated | Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used) | Depth |
|----------------|---|---|-----------|
| 2 | 2710' - 2724' | 1000 gals 15% HCL | 2710-2724 |
| | | 11,100 gals gel & 6,100 lbs 20/40 & 16/30 sand | 2710-2724 |

TUBING RECORD Size 2-3/8 Set At 2746 Packer At None Liner Run Yes No

Date of First, Resumerd Production, SWD or Enhr. November 3, 2008 Producing Method Flowing Pumping Gas Lift Other (Explain)

| Estimated Production Per 24 Hours | Oil Bbls. | Gas Mcf | Water Bbls. | Gas-Oil Ratio | Gravity |
|-----------------------------------|-----------|---------|-------------|---------------|---------|
| | 0 | 103 | 75 | | |

Disposition of Gas Vented Sold Used on Lease (If vented, Submit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify)

Production Interval 2710' - 2724'

W.R. WILLIAMS, INC.
EXPLORATION & PRODUCTION
P.O. BOX 15163 • AMARILLO, TEXAS 79105 • (806) 374-4555

November 20, 2008

RECEIVED
KANSAS CORPORATION COMMISSION

Kansas Corporation Commission
Conservation Division
130 S. Market, Room 2078
Wichita, KS 67202

NOV 24 2008

CONSERVATION DIVISION
WICHITA, KS

Handwritten signature and date: 11/25/08

RE: Prickett #2
Sec. 4-T22S-R40W
Hamilton County, Kansas

KCC

API #: 15-075-20840-0000

Gentlemen:

Per Rule 82-3-107 (e)(1), Please hold the enclosed electric log and ACO-1 confidential for a period of one year.

Sincerely yours,

Handwritten signature of W.R. Williams

W.R. Williams
President

DRILLER'S LOG

W.R. WILIAMS, INC.
PRICKETT #2
SECTION 4-T22S-R40W
HAMILTON COUNTY, KANSAS

COMMENCED: 09-07-08
COMPLETED: 09-09-08

SURFACE CASING: 257' OF 8 5/8" CMTD
W/185 SKS COMMON + 3% CC + 2% GEL

FORMATION

DEPTH

SURFACE
SAND
SANDSTONE & CLAY
RED BED
STONE CORRAL

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 24 2008

CONSERVATION DIVISION
WICHITA, KS

0 - 270'
270' - 321'
321' - 1271'
1271' - 2300'
2300' - 2764' RTD

I DO HEREBY CERTIFY THAT THE FOREGOING STATEMENTS ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

CONFIDENTIAL

NOV 20 2008

KCC

CHEYENNE DRILLING




JACK PEPPER


STATE OF KANSAS: ss:

SUBSCRIBED AND SWORN TO BEFORE ME THIS 25TH DAY OF SEPTEMBER, 2008.

JOLENE K. RUSSELL



NOTARY PUBLIC



ALLIED CEMENTING CO., LLC. 32055

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley, Ks

| | | | | | | | |
|------------------------------------|--------------|--|-----------------|------------|----------------------------|--------------------------|---------------------------|
| DATE <u>9/7/08</u> | SEC <u>4</u> | TWP. <u>22</u> | RANGE <u>40</u> | CALLED OUT | ON LOCATION <u>5:00 pm</u> | JOB START <u>8:45 pm</u> | JOB FINISH <u>9:15 pm</u> |
| LEASE <u>Pricket #2</u> | WELL # | LOCATION <u>Tribune S. TO RD 7 in Hamilton Co.</u> | | | COUNTY <u>Hamilton</u> | STATE <u>Ks</u> | |
| OLD OR NEW (Circle one) <u>NEW</u> | | E 3 S into | | | | | |

CONTRACTOR Trinidad 211
 TYPE OF JOB Surface
 HOLE SIZE 12 1/4 T.D. 270'
 CASING SIZE 8 5/8 DEPTH 266'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. 15'
 PERFS. _____
 DISPLACEMENT _____

CONFIDENTIAL
NOV 20 2008

EQUIPMENT

PUMP TRUCK CEMENTER Alan KCC
 # 422 HELPER Wagner
 BULK TRUCK _____
 # 347 DRIVER Darrin
 BULK TRUCK _____
 # _____ DRIVER _____

OWNER Same

CEMENT
 AMOUNT ORDERED 185 SK, Com 3.070cc
2.070 gel

| | | |
|-------------------------------|----------------|----------------|
| COMMON <u>185 SK</u> | @ <u>15.45</u> | <u>2858.25</u> |
| POZMIX _____ | @ _____ | _____ |
| GEL <u>3 SK</u> | @ <u>20.80</u> | <u>62.40</u> |
| CHLORIDE <u>7 SK</u> | @ <u>58.20</u> | <u>407.40</u> |
| ASC _____ | @ _____ | _____ |
| RECEIVED | @ _____ | _____ |
| KANSAS CORPORATION COMMISSION | @ _____ | _____ |
| NOV 24 2008 | @ _____ | _____ |
| CONSERVATION DIVISION | @ _____ | _____ |
| WICHITA, KS | @ _____ | _____ |
| HANDLING <u>195 SK</u> | @ <u>2.40</u> | <u>468.00</u> |
| MILEAGE <u>104 SK/mile</u> | @ _____ | <u>2086.50</u> |
| TOTAL | | <u>5882.55</u> |

REMARKS:
Cement D. & Circulate
Frank
Alan Wagner, Darrin

SERVICE

| | |
|-----------------------------|-----------------------------|
| DEPTH OF JOB <u>266'</u> | |
| PUMP TRUCK CHARGE _____ | <u>1018.00</u> |
| EXTRA FOOTAGE _____ | @ _____ |
| MILEAGE <u>107</u> | @ <u>7.00</u> <u>749.00</u> |
| MANIFOLD <u>Head Rental</u> | @ _____ <u>113.00</u> |
| TOTAL | <u>1880.00</u> |

CHARGE TO: WR Williams
 STREET _____
 CITY _____ STATE _____ ZIP _____

8 5/8 PLUG & FLOAT EQUIPMENT

| | | |
|----------------------------------|----------------|---------------|
| <u>8 5/8</u> Wooden Surface Plug | @ _____ | <u>68.00</u> |
| <u>Petrow Pattern Guide Shoe</u> | @ <u>1</u> | <u>315.00</u> |
| <u>Centrifuger</u> | @ <u>62.00</u> | <u>62.00</u> |
| TOTAL | | <u>445.00</u> |

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____
 SIGNATURE Joe Brongher

ALLIED CEMENTING CO., LLC. 32058

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Dakley, Ks

| | | | | | | | |
|--------------------------------|------------------|--|-----------------|------------------------|---------------------------|-------------------------|--------------------------|
| DATE <u>9/9/08</u> | SEC. <u>4</u> | TWP. <u>22</u> | RANGE <u>40</u> | CALLED OUT | ON LOCATION <u>2:30pm</u> | JOB START <u>5:15pm</u> | JOB FINISH <u>6:15pm</u> |
| LEASE <u>Procket</u> | WELL # <u>#2</u> | LOCATION <u>Tribune S. To Rd 7 (Hamilton co)</u> | | COUNTY <u>Hamilton</u> | STATE <u>Ks</u> | | |
| OLD OR <u>NEW</u> (Circle one) | | <u>E3 Sinto</u> | | | | | |

CONTRACTOR Trinidad 211

TYPE OF JOB Production string

HOLE SIZE 7 7/8 T.D. 2764'

CASING SIZE 4 1/2 - 10 1/2 lb DEPTH 2769'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG _____

PERFS. _____

DISPLACEMENT NOV 20 2008

OWNER Same

CEMENT

AMOUNT ORDERED 500 SKs Cite 5# Gilsonite, 14 lb Flo seal, 125 SKs Class C

| | | | |
|--------------------------|---|--------------|-----------------|
| COMMON 125 SKs class "C" | @ | <u>19.25</u> | <u>2406.25</u> |
| POZMIX | @ | | |
| GEL | @ | | |
| CHLORIDE | @ | | |
| ASC | @ | | |
| 500 SKs Lite | @ | <u>14.05</u> | <u>7025.00</u> |
| Flo Seal 125 lb | @ | <u>2.50</u> | <u>312.50</u> |
| Gilsonite 2500 lb | @ | <u>.89</u> | <u>2225.00</u> |
| HANDLING 714 SKs | @ | <u>2.40</u> | <u>1713.60</u> |
| MILEAGE 10.4 SK/mile | @ | | <u>2634.80</u> |
| TOTAL | | | <u>21322.15</u> |

EQUIPMENT

PUMP TRUCK CEMENTER Alan

_____ HELPER Wayne

BULK TRUCK DRIVER Darrin

347

BULK TRUCK DRIVER John

John

Wil

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 24 2008
CONSERVATION DIVISION
WICHITA, KS

REMARKS:

Mix 500 SKs Lite 5# Gilsonite 14 lb Flo Seal Tail w/ 125 SKs Class "C" & Airplace w/ 4 1/2 BBL Land Pump @ 2200 lb/hp 1200 L.P.T. Pressure. Float Held Cement Did Circulate

Thank You
Alan, Wayne, Darrin, Wil, John

SERVICE

| | |
|-----------------------------|-----------------------------|
| DEPTH OF JOB | <u>2769'</u> |
| PUMP TRUCK CHARGE | <u>2811.00</u> |
| EXTRA FOOTAGE | @ |
| MILEAGE <u>107</u> | @ <u>7.00</u> <u>749.00</u> |
| MANIFOLD <u>Head Rental</u> | @ <u>113.00</u> |
| TOTAL <u>2873.00</u> | |

CHARGE TO: W R Williams

STREET _____

CITY _____ STATE _____ ZIP _____

4 1/2" PLUG & FLOAT EQUIPMENT

| | | |
|----------------------|-----------------|---------------|
| AFU Float Plug | | <u>434.00</u> |
| Latch Down Ass. | @ | <u>405.00</u> |
| Baskets -2 | @ <u>169.00</u> | <u>338.00</u> |
| Centralizers -8 | @ <u>51.00</u> | <u>408.00</u> |
| TOTAL <u>1585.00</u> | | |

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME _____

SIGNATURE Joe Bronger

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS