

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-06995-00-00

Spot: W2W2NW

Sec/Twnshp/Rge: 25-14S-14W

3960 feet from S Section Line, 4950 feet from E Section Line

Lease Name: BEN REIN

Well #: 3

County: RUSSELL

Total Vertical Depth: 3028 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2923	0	w/unknown sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/01/2010 11:30 AM

Plug Co. License No.: 33930

Plug Co. Name: SUPER OILWELL SERVICE

Proposal Rcvd. from: DAVE FUNK

Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed
Plugging
Method:

Ordered 480 sxs 60/40 pozmix - 4% gel - 700# hulls.
Perf: 1400' - 750' - 366'.

CN#20100030-002

Plugging Proposal Received By: BRUCE BASYE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/01/2010 3:00 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2330' - pumped 170 sxs cement with 300# hulls mixed in.
Pulled tubing to 1400' - pumped 130 sxs cement with 200# hulls mixed in.
Pulled tubing to 700' - pumped 80 sxs cement with 200# hulls - cement circulated.
POOH. Hooked up to casing and pumped 100 sxs cement.
Weak return on backside - no cement return.

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3020.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION

APR 15 2010

CONSERVATION DIVISION
WICHITA, KS

ANOLIND O & G CO.

#3

BEN REIN

25-14-14W
CWL NW

Contr.

RUSSELL

County

E 1780

Comm.

11-8-39

Comp.

1-1-40

IP

30

BOPD, -2 BWPD

Tops	Depth	Datum
ANHY	740	
TARK	2300	
LANS	2918	
TD	3028	

Casing

7" 2923

Old IP 1153 BOPD 10% Wtr
A/6000, SO 2940-45, 2956-
61, 2963-66, 3002-03 &
3020-25: OWPB: PB 2350;
Perf 40/2297-2307; A/500

-	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE