

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-06996-00-00  
Spot: S2SWNW Sec/Twnshp/Rge: 25-14S-14W  
2970 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: BEN REIN Well #: 4  
County: RUSSELL Total Vertical Depth: 3223 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	647	0	w/unknown sxs cmt
PROD 7		2995	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/08/2010 11:30 AM  
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES  
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmxl - 4% gel - 600# hulls - 21 sxs gel.  
Perfs: 1400' - 750' - 600' - 360'.  
  
Control Number: 20100030-003.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/08/2010 5:30 PM KCC Agent: RAY DINKEL

**Actual Plugging Report:**

Ran tubing to 2700' - pumped 14 sxs gel - followed with 100 sxs cement with 200# hulls.  
Pulled tubing to 1400' - pumped 130 sxs cement with 200# hulls.  
Pulled tubing to 700' - pumped 100 sxs cement with 200# hulls - cement circulated.  
POOH. Hooked up to casing - pumped 100 sxs cement.  
Max. P.S.I. 700#. S.I.P. 500#.  
Backside circulated around Braden head - no cement to surface.  
Open casing up - cement down 10'.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3783.

Plugged through: TBG

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 15 2010

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

cm

15-16 7-06996-00-50

STANOLIND O & G CO.

#1

BEN REIN

2970 FSL 25-14-14W  
4620 FEL CSL SW NW

Contr.

RUSSELL

County

E 1769

Comm. 3-11-40

Comp. 4-4-40

IP 704 BOPD &

330 BHPD

Tops	Depth	Datum
ANHY	715	
TOP	2693	
LANS	2906	
B/SD	3156	
TD	3223	PB 3050

Casing  
10" 647  
7" 2995

Pay 2910-15  
SO 3005-16  
3156-3233  
VSSO 2931-42  
PB 3050

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS