

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02779-00-00
Spot: SESENW Sec/Twnshp/Rge: 25-14S-14W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BEN REIN Well #: 10
County: RUSSELL Total Vertical Depth: 2400 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	299	0	w/unknown sxs cmt
PROD	5.5	2390	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2010 8:30 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 305 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf: 1400' - 740' - 350' - 250'.
Control Number: 20100030006.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2010 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report: _____ Perfs: _____

Ran tubing to 2365' - pumped 210 sxs cement with 400# hulls - cement circulated.
POOH. Hooked to casing and pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 450#.
Hooked to Braden head and pumped 10 sxs cement.
Max. P.S.I. 400#.

RECEIVED
SEP 01 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKE #4174.

Plugged through: TBG

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

STANOLIND OIL & GAS CO #10 REIN SE SE NW 25-14-11W

Contr. ----- RUSSELL ----- County

E 1756 ----- Comm. ----- Comp. 1-9-53 ----- IP 33 BOPD & 8 BW

Tops	Depth	Datum	Casing
			8" 299
			5" 2390
TARK	2267	-511	
2ND TARK	2288	-532	
			CO 2400: SANDFRAC
			PERF 2261-76: PERF
			2288-98
			ACID 500

HALL GURNEY POOL

TD 2400 -644

