

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04298-00-01
Spot: SENESE Sec/Twnshp/Rge: 35-18S-12W
1620 feet from S Section Line, 330 feet from E Section Line
Lease Name: ZINK A Well #: 2
County: BARTON Total Vertical Depth: 3465 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	674	0	w/unknown sxs cmt
PROD	4.5	3438	0	w/unknown sxs cmt

Well Type: EOR UIC Docket No: E08376.1 Date/Time to Plug: 08/04/2010 9:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed
Plugging
Method:

Ordered 365 sxs 60/40 pozmix - 4% gel - 400# hulls - 9 sxs gel.

Control Number: 20100031-002

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/04/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perfed at 1450' - 760' - 550'.
Ran tubing to 3200' - pumped 9 sxs gel - followed with 50 sxs cement with 100# hulls.
Pulled tubing to 1450' - pumped 65 sxs cement with 100# hulls.
Pulled tubing to 700' - circulated cement to surface with 80 sxs cement with 200# hulls.
Pulled tubing and pumped 130 sxs cement down casing - circulated out surface pipe.
Shut in.

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

RECEIVED
AUG 18 2010
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

AUG 10 2010

COOPERATIVE REFG ASSN

#2 ZINK 'A'

35-18-12W 53
E2 E2 SE

Contr. SHIELDS DRLG

BARTON County

E 1809RB Comm. 5-4-59

Comp. 6-19-59

IP

40 BOPD

Tops	Depth	Datum
HEEB	2986	-1177
TOR	3009	-1200
DOUG	3024	-1215
BR LM	3102	-1293
LANS	3118	-1309
B/KC	3382	-1573
ARB	3419	-1610
TD	3465	-1656

Casing
8" 674
4" 3438
DST 3104-26/1 HR, 8' MUD, BHP 0#
DST 3132-50/1 HR, 130' G, 50' GCM, SO, BHP
155#
DST 3152-70/1 HR, 60' WTRY M, BHP 70#
DST 3247-75/1 HR, 360' G, 300' H GCM, 120'
H GCM, 300' O, BHP 645#
DST 3279-91/1 HR, 10' M, BHP 760#
PERF 3438-65: ACID 1000: SWB 2 BWPH: PERF
3313-16: BL 3 GWPH & SC O: ACID 500: PERF
3284-87: BL 14 GW, SO: ACID 1000: 1400#
FIH, 98# WTR: 6 BF & 3 GOPH: PERF 3251-54:
BOTTOMS POOL ACID 1000: PERF 3142-46

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS