

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21509-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 25-15S-14W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: DIETZ Well #: 1  
County: RUSSELL Total Vertical Depth: 3342 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250	0	w/unknown sxs cmt
PROD	5.5	3338	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2010 4:30 PM  
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES  
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel.  
Bad casing and got out of pipe.

Control Number: 20100071-001.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 03/01/2010 6:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 880' - last three joints tight - pumped 200 sxs cement - cement circulated.  
POOH. Hooked to casing and pumped 40 sxs cement.  
Max. P.S.I. 800#.  
Hooked to Braden head and pumped 15 sxs cement.  
Max. P.S.I. 500#.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3705.

Plugged through: TBG

District: 04

Signed

*Ray A Dinkel*

(TECHNICIAN)

CM

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 15 2010

CONSERVATION DIVISION  
WICHITA, KS