

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21734-00-00
Spot: SENWSW Sec/Twnshp/Rge: 25-15S-14W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: DIETZ Well #: 4
County: RUSSELL Total Vertical Depth: 3340 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250	0	w/170 sxs cmt
PROD	5.5	3337	0	w/200 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2010 8:00 AM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVE FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 315 sxs 60/40 pozmix - 4% gel - 600# hulls - 8 sxs gel.
Perfs: 1660' - 890' - 410'.

Control Number: 20100071-002.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2010 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3120' - pumped 8 sxs gel - followed with 75 sxs cement with 300# hulls.
Pulled tubing to 1700' - pumped 90 sxs cement with 200# hulls.
Pulled tubing to 850' - pumped 90 sxs cement - cement circulated.
POOH. Hooked up to casing and pumped 5 sxs cement.
Max. P.S.I. 450#.
Hooked up to Braden head and pumped 5 sxs cement.
Max. P.S.I. 350#.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3782.

Plugged through: TBG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 15 2010

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM