

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19346-00-01

Spot: NENENE

Sec/Twnshp/Rge: 24-14S-15W

4950 feet from S Section Line,

330 feet from E Section Line

Lease Name: EICHMAN OWWO

Well #: 2

County: RUSSELL

Total Vertical Depth: 3232 feet

Operator License No.: 101

Op Name: KCC FEE FUND PLUG

Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	12	525	0	w/unknown sxs cmt
PROD	5.5	3231	0	w/unknown sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/26/2010 8:00 AM

Plug Co. License No.: 32528

Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES

Proposal Rcvd. from: DAVE FUNK

Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed
Plugging
Method:

Ordered 150 sxs 60/40 pozmix - 4% gel - 300# hulls.

Perf: 900' - 410' - 150'.

Control Number: 20100073-001

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/26/2010 10:00 AM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 930' - pumped 50 sxs cement - followed with 50 sxs cement with 300# hulls - cement circulated.

POOH. Hooked to casing - pumped 10 sxs cement.

Max. P.S.I. 600#.

Braden head dug out cement in between 5 1/2" and 8 5/8" casing.

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4173.

Plugged through: TBG

RECEIVED

SEP 03 2010

KCC WICHITA

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

AUG 31 2010

24-14-15W
NE NE NE

CONTRACTOR: Ivan Holt Well Serv., Inc., City Russell

GEOL _____ FIELD GORHAM

E 1817 GL CM ?/78 CARD ISSUED 2/24/79 IP OIL WELL

ARB OH 3231-3237

API NOT ASSIGNED

[illegible]

**INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS**

OLD INFO: OPERATOR WAS J.W. BRADEN
DRLG. CO. #2 REINHARDT; SPD 6/8/50,
SET 12" 525, 5" 3231; COMPLETED FOR
65BOPD/8/25/50
MFCI - CO. (ARB O.H.), AC 150, 800'
OIH/12HRS, RB 3210, PF 24/3169-73,
AC 500, 2BOPH, AC 4000, SWB 2B0 +
4BWPH, SQZ & CO 3232, POP, P 40BOPD
NEW INFO: RE-ENTERED 1978, WSH DWN,
DD 3237 TD, (ARB OH), TSTD, POP, OIL
WELL, NO OTHER INFO RELEASED

J. W. BRADEN DRILLING COMPANY #2 REINHARDT

24-14-15W.
NE NE NE 33

Contr. _____ RUSSELL County

E 1817 Comm. 6-8-50 Comp. 8-25-50 IP 65 BORD

Tops	Depth	Datum
ANH	847	+970
LANS	3110	-1293
ARB	3229	-1412
TED	3232	

**INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS**

Casing

12" 525 ACID 150: 800' Q1H/12
5" 3231 HRS: PB 3210: PERF 24 S
3169-73: ACID 500:
 $\frac{1}{2}$ BOPH: ACID 4000:
SWB $\frac{1}{2}$ BP & 4 BPH: SQZ
& CO 3232: PMP 40 BOPD

BIG CREEK POOL