

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20380-00-00
Spot: SWSE Sec/Twnshp/Rge: 6-1S-34W
560 feet from S Section Line, 1980 feet from E Section Line
Lease Name: DOZBABA Well #: 1
County: RAWLINS Total Vertical Depth: 4330 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

RECEIVED
JUL 29 2010
KCC WICHITA

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	283	0	w/225 sxs cmt
PROD	4.5	4318	0	w/525 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/19/2010 11:00 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: SCOTT SCHIPPERS Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: 07/19/2010 - Ordered 375 sxs 60/40 pozmix - 4% gel - 500# hulls - 9 sxs gel spacer. Plug through tubing.
07/23/2010 - Ordered 225 sxs 60/40 pozmix - 4% gel - 400# hulls.
Control Number: #20100017-001

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2010 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 283' w/225 sxs cement.
4 1/2" production casing set at 4318' w/525 sxs cement.
Port collar cemented - depth not available. Casing had holes.
07/19/2010 - Ran tubing to 3992' - pumped 9 sxs gel - followed with 50 sxs cement mixed with 150# hulls.
Pulled tubing to 2250' - pumped 50 sxs cement mixed with 100# hulls.
Pulled tubing to 1100' - pumped 275 sxs cement - good returns - cement did not circulate.
Pump truck experienced pump problems during the plugging process.
07/23/2010 - Contacted cement with tubing at 1175'.
Loaded hole with water prior to pumping 100 sxs cement - cement to surface.
Pulled tubing to surface.
Connected to 8 5/8" surface casing - pumped 50 sxs cement.

Perfs:

Top	Bot	Thru	Comments
4242	4243		
4107	4109		
4066	4077		
3927	3931		

Remarks: S.O.S. CEMENTING COMPANY-TICKET #455 & 456. ENERGY SEARCH SERVICE UNIT.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

JUL 26 2010

WILLIAM E WISE
 46 B DENVER TECH-CENTER
 ENGLEWOOD, CO 80111
 #1 DOZBABA 100'S, C SW SE 6-1-34W
 CONTR PRAIRIE DRILLING CTY RAWLINS
 GEOL JOE BATO FIELD CAHOJ NW
 E 3129 KB CM 6/23/80 CARD ISSUED 11/20/80 IP D&A/PENN
 3118 GL 15-153-20,380

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		3006	+ 123
RED E		3572	- 443
FOR		3624	- 495
TOP		3837	- 708
DR CR		3875	- 746
OREAD		3927	- 798
LKC		4047	- 918
BKC		4314	-1185
LTD		4330	-1201

8-5/8" 283/225sx, 4 1/2" 4318/525sx
 DST (1) 4241-4253 (LKC)/15-45-30-60,
 REC 240' GSY O, 60' O&W, (20% O),
 1600' WTR, SIP 835-835#, FP 146-
 596/606-793#
 DST (2) 4213-4222 (LKC)/15-45-15-30,
 REC 3' M, SIP 902-939#, FP 5-5/
 5-5#
 DST (3) 4196-4205 (LKC)/20-45-10-30,
 REC 20' M, SIP 949-835#, FP 31-31/
 42-42#

(OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

WILLIAM E. WISE #1 DOZBABA 100' S, C SW SE 6-1-34W

MICT - CO, PF (LKC) 4242-43, AC 250 G,
 SWB LD & REC 9 BFPH, 5% O, SET BP @
 4204, PF (LKC) 4066-70, AC 500 G, SWB
 LD & SWB .9 BFPH, 3% O, PF (LKC)
 4107-09, SWB 1.6 BFPH, 2% O, PF (OREAD)
 3927-31, SWB 12 BFPH, TR O, SD-
 PROD NON-COMMERCIAL, P&A - MAY
 CONVERT TO SWDW AT A LATER DATE