

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03271-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 25-15S-18W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: WOLF Well #: 1  
County: ELLIS Total Vertical Depth: 3506 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	0	0	0	0
PROD	5.5	3504	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/28/2010 12:00 PM  
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE  
Proposal Rcvd. from: DAVID FUNK Company: KANSAS CORPORATION COMMIS Phone: (785) 625-0550

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 12 sxs gel.  
Shoot perms at 1800' - 1150' - 450' - 150'.  
CN 20100020-001

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/28/2010 3:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Shot perms at 1800' - 1150' - 450' - 150'.  
Ran tubing to 3000' - pumped 12 sxs gel - followed with 50 sxs cement and 200# hulls.  
Pulled tubing to 1800' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 1100' - pumped 100 sxs cement with 100# hulls - good circulation of cement.  
Pulled tubing out - tied onto 5 1/2" - pumped 10 sxs cement.  
Shut in at 350# P.S.I. Full.  
Tied onto the 8 5/8" - pressured to 350# P.S.I. Full.

RECEIVED  
KANSAS CORPORATION COMMISSION

FEB 01 2010


CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3719.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

DON PRATT

#1 WOLF

25-15-18W 34  
NW NW NW

Contr.

ELLIS

County

E 1918

Comm. 3-1-53

Comp. 4-24-53

IP 144 BOPD

Tops	Depth	Datum
HEEB	3137	-1219
LANS	3196	-1278
ARB	3498	-1580
TD	3506	-1588

Casing  
5" 3504

CO 3506, 10 BOPD

BEILMAN POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS