

3 023424

15-001-02507-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 100 101Operator: STATE OF KANSASName & FEE FUND PLUGGING

Address \_\_\_\_\_

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE, LLCLic. # 30670Address: 19245 FORD RD., CHANUTE, KS. 66720Company to plug at: Hour: 1:00P.M. Day: \_\_\_\_\_ 12 Month: 8 2008Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL ORIGINALLY CONSISTED OF 2" CASING TO 850' THAT MAYHAVE BEEN PLUGGED. THE PLUGGING PROPOSAL WAS TO DRILL OUT THE WELLTO 200' AND CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: \_\_\_\_\_

CLAYTON P. TITELPlugging attended by Agent: All X Part \_\_\_\_\_TECHNICIAN  
None \_\_\_\_\_Operations Completed: Hour: 3:00P.M. Day: \_\_\_\_\_ 12 Month: 8 2008Actual Plugging Report: THE 2" CASING WAS DRILLED OUT TO 225'. AT THATDEPTH THE BIT WAS STILL IN SOLID CEMENT. THE CASING WAS PERFORATED AT60' AND PERFORATED AT 210'. 1" PIPE WAS RAN INTO THE 2" CASING TO 225'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLEDFROM SURFACE. 21 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION POINT NO. 10) (THIS WELL WAS NO. C-17 ON THE LEASE MAP.)(If additional description is necessary, use BACK of this form.)Control # 20080046-010I DID observe this plugging.

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 25 2008  
CONSERVATION DIVISION  
WICHITA, KS

Signed: \_\_\_\_\_

Clayton P. Titel  
TECHNICIAN

KCCPCT per  
Logan & PS  
Lee fund  
database

API NUMBER

SE 1/4, SE 1/4

SE 1/4, SE 1/4

Sec/Twp/Rge S.14-T.26S.-R.18E.40 feet from south section line1505 feet from east section lineLease/Well# LOCKHART NO. C-17

(LOC-10)

County ALLENWell Total Depth 850 feetProduction Pipe: 2" Size Feet 850Surface Casing: 8" Size Feet 20'E-591 D & A

**Clayton Titel***Att: Pam Thorne*

**From:** Pam Thorne  
**Sent:** Wednesday, March 11, 2009 11:03 AM  
**To:** Clayton Titel  
**Subject:** FEE FUND

Clayton I received a fee fund from you for the Lockhart No. c-17. Gps session point no. 10. this well was no C-17 on the lease map. We have two footages. could you please tell me which ones are correct. Bob has a copy of the projects which shows this lease as SESWSE 14-26-18E 0 FSL 54 FEL. You have 1981 SESWSE 14-26-18E 1981 FSL 633 FEL. Bob Jenkins said to email u to verify which is correct. Thanks

*Pam Thorne*  
Senior Administrative Assistant  
Kansas Corporation Commission  
Conservation Division  
130 S. Market, Room 2078  
Wichita, KS 67202-3802  
Phone 316-337-6236 Fax- 316-337-6211  
[pthorne@kcc.ks.gov](mailto:pthorne@kcc.ks.gov)

*Spot location is:*

*1505' N.E.L.  
410' N.S.L. of 14-26-18E Al. Co  
SE, SE, SW, SE  $\frac{1}{4}$*

*Preceding is result of LEO 7 process of  
D.P.S. reading of original D.P.S. reading  
of 37.7765322 & 95.4024219.*

*C. P. T.*

*5/20/09*

RECEIVED

MAY 26 2009

KCC WICHITA

5/20/2009