

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-073-01104-00-00
se-ne-nw Sec/Twp/Rge 22-25-11 e
4583' feet from south section line
2765' feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease/Well# parks #2County greenwoodOperator: state of kansasWell Total Depth 1650' feet

Name & _____

Production Pipe: 4.5" Size Feet 1650'

Address _____

Surface Casing: 8 5/8" Size Feet uknAB oil well xxxxxxx Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: k w oil well ser. Inc. Lic. # 30670Address: 19450 ford rd. chanute, ks. 66720

Company to plug at: Hour: _____ Day: _____ 15 Month: _____ 6 2009

Plugging proposal received from: _____

Company Name: _____ Phone: _____

Were: 50' cement plug @ 1450' 50' cement plug @ 800' 150' cement plug to surface.

KANSAS CORPORATION COMMISSION

JUN 24 2009

RECEIVED

Plugging Proposal Received by: mike heffernTECHNICIAN
NonePlugging attended by Agent: All xxxxxxx Part _____

Operations Completed: Hour: _____ Day: _____ 16 Month: _____ 6 2009

Actual Plugging Report: ran tubing to 1450' pumped 20 sxs cement, shot casing @ 650'ran tubing to 650' pumped 20 sxs cement, shot casing @ 150' pumped 57 sxs cement to surface, gelspacers between cement plugs, empty close pit cut off well head.Remarks: control#20090033-002 contract # 11782

(If additional description is necessary, use BACK of this form.)

I observe this plugging.

Signed:

Mike Heffern
TECHNICIAN