


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SE/SW" or footage from lines Ellis County. Sec. 8 Twp. 13S Rge. 16 (E) (W)
SE SE NE
Lease Owner Terrel Drilling & Producing
Lease Name Weigle Well No. 1
Office Address Box 606, Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-6 19 63
Application for plugging filed 10-6 19 63
Application for plugging approved 10-6 19 63
Plugging commenced 10-6 19 63
Plugging completed 10-6 19 63
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3505 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	133	8 5/8	133	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 480', plug $\frac{1}{2}$ sack hulls,
20 sacks cement. Heavy mud to 180', plug $\frac{1}{2}$ sack hulls,
20 sacks cement. Mud to 30', $\frac{1}{2}$ sack hulls, 10 sacks
cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1963

10-09-1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Terrel Drilling and Producing
Address Box 606, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Joe K. Branum (employee or owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Russell, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 7th day of October, 19 63

My commission expires 12-12-66

Notary Public.

15-051-01552-00-00

W E L L L O G

OPERATOR: Terrel Drilling & Producing
Box 606 Russell, Kansas

CONTRACTOR: Company Tools

LEASE: Weigle #1

COMMENCED: September 27, 1963

LOCATION: SE SE NE Sec.8-13S-16W
Ellis County, Kansas

COMPLETED: October 6, 1963

DEPTHS & FORMATIONS

Shale & Shells	133	Shale, Lime & Shells	2730
Shale & Sand Streaks	390	Shale & Lime	2910
Shale & Shells	1070	Lime & Shale	3000
Anhydrite	1090	Lime	3155
Shale & Lime Streaks	1168	Lime & Shale	3225
Shale & Shells	1750	Lime	3266
Lime & Shale	2375	Lime & Shale	3325
Shale & Lime	2525	Lime	3395
Shale w/Lime Streaks	2640	Lime & Shale (R.T.D.)	3505

STATE OF KANSAS

COUNTY OF RUSSELL ss..

Joe K. Branum, owner of Terrel Drilling and Producing, being first duly sworn on oath says: "That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct."


Joe K. Branum-TERREL DRILLING & PRODUCING

Subscribed and sworn before me this 7th day of October, 1963.


Notary Public

My Commission Expires December 12, 1966.

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1963
10-09-1963
CONSERVATION DIVISION
Wichita, Kansas