


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-051-01255-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 8 Twp. 13S Rge. 16 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Franco Central Oil Company
Lease Name Klaus Well No. 1
Office Address Fourth National Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed February 28 19 58
Application for plugging filed February 28 19 58
Application for plugging approved February 28 19 58
Plugging commenced February 28 19 58
Plugging completed = February 28 19 58
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3560 Feet
Show depth and thickness of all water, oil and gas formations. ANB
ca

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	266'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug @ 500'. Put 20 sacks of cement through drill pipe on bottom plug.
Set middle plug @ 200'. Put 20 sacks of cement through drill pipe on middle plug.
Set top plug @ 40'. Put 1/2 sack of Hulls and 10 sacks of cement on top plug. Filled to base of cellar.

03-07-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173 - Russell, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
George A. Angle (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle
580 Fourth National Bank Building-Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 58

My commission expires 11-17-58

Marlene Head
Notary Public.

PLUGGING
FILE SEC 8 T 13 R 16
BOOK PAGE 87 LINE 24

15-051-01255-00-00

DRILLERS LOG

No. 1 Klaus

CASING RECORD: COMPANY: Franco Central Oil Co. DESCRIPTION: NE NE SW
8-5/8" @ 266* CONTRACTOR: Red Tiger Drilling Co. 8-13S-16W
w/150 sx cement Ellis County
Kansas
COMMENCED: February 21, 1958
TOTAL DEPTH: ELEVATION: 1964 DF
3560 (-1593) COMPLETED: February 28, 1958 1967 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock and Clay	0	75	
Blue Shale and Shells	75	263	
Shale and Shells	263	415	
Shale and Redbed	415	560	
Sand and Shale	560	770	
Shale and Shells, Redbed	770	1085	
Shale and Shells	1085	1115	
Anhydrite	1115	1150	
Shale and Shells	1150	1800	
Lime and Shale	1800	2290	
Shale and Shells	2290	2530	
Shale and Lime	2530	2835	
Shale and Shells	2835	2925	
Lime and Shale	2925	3105	
Lime	3105	3470	
Lime and Conglomerate	3470	3545	
Conglomerate	3545	3560	
Arbuckle	3528	3560	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 5th day of March, 1958.

Mariani Head
Notary Public

My Commission Expires:

11-17-58

RECEIVED
STATE CORPORATION COMMISSION

MAR 7 1958
03-07-1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 8 T. 12 R. 14
BOOK PAGE 87 LINE 24