

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 11 TWP. 13 RGE. 16W E/W
Location as in quarters or footage from lines:

NW NE NW

Lease Owner V. Francis Weigel

Lease Name Schmeidler A-1 Well No. _____

Office Address Box 244 Corham, Kansas 67640

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 2-16-82

Plugging completed 2-19-82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation _____ Depth to top _____ bottom T.D. 3510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	151'	none
				4-1/2"	3500'	1133'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

~~Plugged off bottom with sand to 3100' and ran 4 sacks cement. Shot casing @2700', 2600' and 2525'. Came loose @2525', but hung up again. Shot loose again @1139' and pulled a total of 35 joints of pipe. Plugged well with 5 sacks hulls, 19 sacks gel, 8-5/8" plug 140 sacks 50/50 pos, 4% gel, 3% cc. Plugging Complete.~~

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 19 82

My Commission expires:



Irene Hoover
Notary Public.

L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company V. Francis Weigel
 Box 244
 Gorham, Kansas 67640

Farm Schmeidler A No. 1

Total Depth 3510'

Comm. 12-27-68 Comp. 1-4-69

Contractor L. J. Dreiling & Sons, Inc.
 Victoria, Kansas 67671

Sec. 11 Twp. 13 Rng. 16

Location NW NE NW

County Ellis

Elevation: 1963' K. B.
 1960' D. F.
 1958' G. R.

Production:

Casing Record

Cement Record

151' - 8 5/8" 100 sacks cement
 3509' - 4 1/2" 9 1/2" 200 sacks cement

Figures Indicate Bottom of Formations

0'	70'	Clay & Sand
70'	151'	Blue Shale
151'	154'	Shale
154'	650'	Shale & Sand
650'	720'	Sand
720'	1080'	Redbed
1080'	1119'	Anhy.
1119'	1385'	Shale
1385'	1850'	Shale & Shells
1850'	3125'	Shale & Lime
3125'	3510'	Lime

RECEIVED
 STATE CORPORATION COMMISSION
 FEB - 1 1982
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Schmeidler #1.

Leo F. Dreiling
 LEO F. DREILING



Subscribed and sworn to before me this 6th day of January 1969.

Joseph A. Hess
 JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970