


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

15-DSI-20284-00-00

Form CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Ellis County. Sec. 11 Twp. 13 Rge. 16 (E) W (W)
Lease Owner V. Francis Weigel
Lease Name Reidel Well No. 1
Office Address Box 244, Gorham Kansas 67640
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-26 1968
Application for plugging filed 7-26 1968
Application for plugging approved 7-26 1968
Plugging commenced 7-26 1968
Plugging completed 7-26 1968
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3440 Feet
Show depth and thickness of all water, oil and gas formations. Aug 68

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	158'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st. plug was set @ 500' with 70 sacks cement
2nd. plug was set @ 180' with 20 sacks cement
3rd. plug was set @ 40' with solid bridge and 10 sacks cement


RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1968
CONSERVATION DIVISION
Wichita, Kansas
07-30-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
Address Route 2, Victoria, Kansas 67671

STATE OF KANSAS, COUNTY OF ELLIS, ss.
I, Leo F. Dreiling (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671
(Address)

Subscribed and sworn to before me this 27th day of July, 19 68
June 23, 1969



Dorothy A. Werth
Notary Public.
(Rush County, Kansas - Adjoining County)

L. J. DREILING and SONS, Inc.

VICTORIA, KANSAS

WELL LOG

Company	V. Francis Weigel Box 244 Gorham, Kansas 67640	Sec. 11	Twp. 13	Rng. 16
Farm	Reidel No. 1	Location	SW SE SW	
Total Depth	3440'	County	Ellis	
Comm.	7-20-68 Comp. 7-26-68	Elevation:	1935' K.B.	
Contractor	L. J. Dreiling & Sons, Inc. Route 2 Victoria, Kansas 67671		1932' D. F.	
	Casing Record	Production:	1930' G. R.	
	158' - 8 5/8" -	Cement Record	D & A	
		100 sacks cement		

Figures Indicate Bottom of Formations

0'	30'	Top soil & Clay
30'	45'	Post Rock
45'	134'	Shale & Rock
134'	158'	Blue Shale
158'	360'	Shale
360'	480'	Redbed
480'	600'	Shale & Redbed
600'	690'	Sand
690'	1055'	Shale
1055'	1094'	Anhy.
1094'	1720'	Shale & Shells
1720'	2270'	Shale & Lime
2270'	2585'	Shale
2585'	2775'	Shale with Lime Streaks
2775'	2950'	Shale & Lime
2950'	3030'	Lime
3030'	3135'	Lime & Shale
3135'	3440'	Lime
3440'	T.D.	

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1968
CONSERVATION DIVISION
Wichita, Kansas
07-30-1968

STATE OF KANSAS)
) ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Reidel #1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 27th day of July 1968.

Dorothy A. Werth
Dorothy A. Werth - NOTARY PUBLIC
(Rush County, Kansas - Adjoining County)

