

15-051-30192-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Ellis County, Sec. 13 Twp. 13 Rge. 16 (E) (W)X

Location as "NE/CNW%SW%" or footage from lines C of SW SE
Lease Owner A. L. Abercrombie, Inc.
Lease Name Polcyn "B" Well No. #1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-16-66 19
Plugging completed 2-21-66 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker
Producing formation Depth to top Bottom Total Depth of Well 3450' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 3150'.
Mudded hole to 310', set 10' rock bridge, mixed and ran 5 sacks cement thru dump bailer.
Filled hole with 4 yards ready-mix from 300' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1966
00-247904
DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer - Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 22 day of February, 19 66

Sidney D. Miller
Notary Public.

My commission expires 24 October 1968



15-051 - 30192 - 00-00

CONTRACTOR'S WELL LOG

COMPANY:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
FARM:	POLCYN B #1
LOCATION:	SW SE Section 13-13S-16W Ellis County, Kansas
COMMENCED:	October 29, 1964
COMPLETED:	November 7, 1964

0	50	Rock and clay
50	200	Clay and sand
200	625	Shale
625	695	Sand
695	819	Shale
819	1039	Shale and shells
1039	1074	Anhydrite
1074	1115	Shale
1115	1675	Shale and shells
1675	2855	Shale and lime
2855	2913	Lime and shale str.
2913	3581	Lime
3581	3450	Lime and shale
	3450	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1966
02-09-1966
CONSERVATION DIVISION
Wichita, Kansas

Set 8-5/8" Surface casing at 287' w/125 sx cement

Set 4-1/2" casing at 3449' w/150 sx common cement w/2700# salt

ELEVATION: 1953' D.F. & K.B.
1947' G.L.

ELECTRIC LOG TOPS:

Topeka	2868'	(-915)
Heebner	3088'	(-1135)
Toronto	3109'	(-1156)
Lansing	3142'	(-1189)
Base Kansas City	3378'	(-1425)

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the POLCYN B #1, SW SE Section 13-13S-16W, Ellis County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

B. Lynn Herrington
B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 12th day of November, 1964.

Leah Faye Hefke
Leah Faye Hefke, Notary Public

My commission expires June 16, 1967.

