


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ellis County, Sec. 11 Twp. 13 Rge. 16 E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SW SE NW

Lease Owner V. Francis Weigel  
Lease Name Schmeidler Well No. 2  
Office Address Gorham, Kansas 67640  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Date Well completed April 3 1981  
Application for plugging filed " 19  
Application for plugging approved " 19  
Plugging commenced " 19  
Plugging completed " 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation Depth to top Bottom Total Depth of Well 3,435  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	166'	Cmtd w/120 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Fill hole w/heavy mud
- Push bridge plug to 720'
- Spotted 60 sax cement on plug thru 4 1/2" drill pipe
- Fill hole w/heavy mud
- Push bridge plug to 210'
- Spotted 40 sax cement on plug thru 4 1/2" drill pipe
- Push bridge plug to 40' w/1/2 sax hulls on plug
- Dump 10 sax cement on plug to cello
- Dump 5 sax cement in rat hole and 5 sax cement in mouse hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.  
Shields Bldg., Russell, Kansas 67665

RECEIVED  
STATE CORPORATION COMMISSION  
APR 13 1981  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Russell, ss. contractor  
R. L. Shields (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. L. Shields  
Shields Bldg., Russell, Kansas 67665  
(Address)

SUBSCRIBED AND SWORN TO before me this 8 th day of April, 19 81

Luick Phillips  
Notary Public.

My commission expires

ROBERT PHILLIPS  
STATE NOTARY PUBLIC  
RUSSELL COUNTY, KS  
My Appt. Exp. 5-26-83



# Shields


15-051-22327-00-00

Russell, Kansas

## WELL LOG

Operator: V. F. Weigel  
 Well: Schmeidler #2  
 Commenced: March 26, 1981  
 Completed: April 3, 1981  
 Contractor: Shields Drilling Co., Inc.

Well Description: SW SE NW



Sec. 11-13S-16W  
 Ellis Co., Kansas

Elevation: 1,945' KB

Treatment:

Production: D & A

Tops:

### CASING RECORD

Size	Run	Pulled
8 5/8"	166'	Cmtd w/120 sax

..... Figures Indicate Bottom of Formations .....

Surface clay & shale	170'
Shale	340'
Sand	450'
Shale & redbed	1,005'
Shale	1,062'
Anhydrite	1,100'
Shale & shells	1,530'
Shale	1,695'
Shale & lime	2,870'
Lime	3,435' RTD

RECEIVED  
 STATE CORP. COMMISSION  
 APR 13 1981  
 04-13-1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

Notes