

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-05503-00-00

LEASE NAME Hadley

WELL NUMBER A-5

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 20 TWP. 11 RGE. 17W (E) or (W)

COUNTY Ellis

Date Well Completed

Plugging Commenced 4-27-93

Plugging Completed 4-30-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Patton Oil Company

ADDRESS 672 West. 4th St. Hoisington, Ks. 67544

PHONE# (316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Bruce Bayse (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3543'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1146'	none
				5-1/2"	3499'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 3350' and 5 sacks cement. Shot pipe @2800', 2600', 2500', 2300', 2000', pulled to 1900', pumped 35 sacks cement, pumped 25 sacks cement @1200', pumped 100 sacks @640', pulled to 220' and and circulated cement to surface.
Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Patton Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 6th day of May

Irene Herzberg
Notary Public

My Commission Expires:



RECEIVED
MAY 10 1993
STATE CORPORATION COM
CONSERVATION DIVISION
WPSA
Revised 8-88
Kansas

15-051-05503-00-00

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- MURFIN DRILLING CO.
Farm- Hadley "A" No. 5

SEC. 20 T. 11 R. 17W
NW SE NW

Total Depth. 3543'
Comm. 6-2-58 Comp. 6-13-58
Shot or Treated.
Contractor. Murfin Drlg.
Issued. 1-10-59

County Ellis
KANSAS



Elevation. 1894' RB

Production. 25 BOPD

Figures indicate Bottom of Formations.

shale & shells	442
sand & shale	535
iron - pyrite - hard sand	620
iron - hard sand	650
sand & shale	790
red bed - shale	1134
Anhydrite	1168
red bed - shale & shells	1505
salt & shale	1690
shale & shells	1775
lime & shale	2970
lime	3340
lime & shale	3400
Arbuckle lime	3495 RTD
lime ?	3543
Total Depth	

K. G. S. LIBRARY

TOPS:	
Anhydrite	1135
Topeka	2840
Heebner	3079
Kansas City	3124
Arbuckle	3398

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1993

CONSERVATION DIVISION
Wichita, Kansas