

API NUMBER 15-051-01449-0000

LEASE NAME Hadley "C"

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 20 TWP. 115 RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 8-25-88

Plugging Commenced 8-27-88

Plugging Completed _____

LEASE OPERATOR Union Pacific Resources Company

ADDRESS 1000 Louisiana, Suite 3000, Houston, TX 77002-5016

PHONE# (713) 654-2500 OPERATORS LICENSE NO. 6417

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Aug. 11, 1988 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3386' Bottom 3391' T.D. 3391'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS **RECEIVED** RECORDS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				16"	120'	none
				7"	3387'	none
				4 1/2"	2901'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RU Halliburton. Pump 5 sx hulls, 275 sx 60-40 Pozmix down 4-1/2" casing w/6% gel and 3% CaCl2 @ 200#. Pumped 10 sx 60-40 Pozmix down 16" conductor. 7" casing now full of cement. Total 285 sx cement. KCC representative Gilbert Scheck on location. Cut off hanger and 4-1/2" and 7" casing. Weld steel plate on. Cement to top of 16". File cellar and clean up location. Well is
 (If additional description is necessary, use BACK of this form.) P & A.

Name of Plugging Contractor Halliburton License No. 5287

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Union Pacific Resources Company

STATE OF Texas COUNTY OF Harris, ss.

Marilyn Day (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Marilyn Day

(Address) 1000 Louisiana, Suite 3000, Houston, TX 77002

SUBSCRIBED AND SWORN TO before me this 31st day of October, 19 88

Adela Zavala
 Notary Public

Commission Expires: 5-6-91

