

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-22338-0020

LEASE NAME Hadley

WELL NUMBER B#3

SPOT LOCATION NE NW SW

SEC. 20 TWP. 11S RGE. 17W (E) or (W)

COUNTY Ellis

Date Well Completed _____

Plugging Commenced 2-26-86

Plugging Completed 2-26-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Patton Oil Company

ADDRESS 672 W. 4th Hoisington, Kansas 67544

PHONE # (316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	212'	none
				5-1/2"	3498'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plug Job Only - No Pipe Recovery Pumped down 5-1/2" casing, 4 hulls, 25 cement, 15 gel, 1 hull, released plug and 110 sks. cement, 60/40 pos, 6% gel, 3% cc. Couldn't pump into backside of 8-5/8" casing. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

MAR 5 1986
03-05-86
CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso
(Address) P.O. Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 1986

Irene Hoover
Notary Public

My Commission expires:



BIG SPRINGS DRILLING, INC.

P.O. BOX 8287
MUNGER STATION
WICHITA, KANSAS 67208

SUITE 29 • 400 NORTH WOODLAWN • (316) 681-1732

April 8, 1981

DRILLERS LOG

Re: Hadley "B" #3
NE NW SW
Sec. 20 Twp 11S Rg 17W
Ellis County, Kansas

OPERATOR: Patton Oil Company
CONTRACTOR: Big Springs Drilling, Inc.
COMMENCED: March 29, 1981
COMPLETED: April 5, 1981

Surface Pipe: Set 213' of 8 5/8" w/150 SX Common 2% gel 3% ccl

0	213'	Sand, Clay & Shale
213'	1133'	Shale
1133'	1171'	Anhydrite
1171'	2340'	Shale
2340'	3390'	Shale & Lime
3390'	3500'	Lime
3500'		RTD

We certify that the above and foregoing is a true and correct copy of the log on the Haldey "B" #3 located in Ellis County, Kansas.

Big Springs Drilling, Inc.

Paul A. Seymour III
Paul A. Seymour, III

Subscribed and sworn to before me this 8th day of April, 1981.

My Commission Expires:
May 30, 1983

RUTH M. BASSETT
STATE NOTARY PUBLIC
Sedwick County, Kansas
My Appt. Exp. _____

Ruth M. Bassett
Ruth M. Bassett Notary Public