

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-107-20497-00-00
Spot: SENESESW Sec/Twnshp/Rge: 21-19S-23E
706 feet from S Section Line, 2880 feet from E Section Line
Lease Name: BALDWIN Well #: 21L22
County: LINN Total Vertical Depth: 300 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2010 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: MIKE KEPLEY Company: _____ Phone: _____

Proposed Plugging Method: FILL WELL WITH CEMENT FROM TD TO SURFACE THEN SQUEEZE.

Plugging Proposal Received By: LEVI SHORT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed 02/26/2010 5:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

Perfs:

RUN 1 INCH INSIDE 2 INCH CASING TO 300 FEET AND RUN 1/2 INCH OUTSIDE 2 INCH CASING TO 26 FEET THEN PUMP PORTLAND CEMENT FROM TD TO SURFACE. PULL PIPE AND SQUEEZE TO 325 POUNDS PRESSURE. PUMP TOTAL OF 16 SACKS OF CEMENT.

RECEIVED

MAR 22 2010 LS

KCC Chanute Dist. #3

RECEIVED

APR 05 2010

KCC WICHITA

Remarks: Control #: 20100027-007 / GPS #: BAL 007 / Contract #: 12596

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)