

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1978
03-22-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -051-02245-0000 (of this well)

Operator's Full Name Patton Oil Company

Complete Address Greenwood Plaza No.-5660' S. Syracuse Circle, Suite 200
Englewood, Colorado 80110

Lease Name Peavey A DUB XCC Well No. 5

Location SE NE NE NESE NE Sec. 19 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3565'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 2 P Day 20 Month 3 Year 1978

The above well was plugged as follows:

Total Depth 3565' .8 5/8 csg set 1230' cwc 525 sk.

5 1/2 csg set 3564' cw 100 sk cem.

5 1/2 csg PBSD 3555' with perf. (3536'-3274')

Filled 5 1/2 csg with sand (3555'-3250') dumped 4 sk cem W/dump bailer. (3250'-3220')

Cutoff & recovered 2507' of 5 1/2 csg.

Set rock & sand bridge at 350' -filled to surface with readymix cement

I hereby certify that the above well was plugged as herein stated.

Signed: Geo Massey
Well Plugging Supervisor

DATE 3-23-78
INV. NO. 6978-c