

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

AUG 15 1974

CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Sun Oil Company

Complete Address 800 Security Life Bldg., Denver, Colorado 80202

Lease Name Peavy "D" Well No. 2

Location W/2 SW NW Sec. 19 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3361'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Chas Crowe Pipe Pulling

Address Hays, Kansas License No. 733

Operation Completed: Hour 11:30 A Day 10 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3361' 8 5/8 csg set at 1110' cwc 600 sk--13 3/8 csg set at 120' cwc  
5 1/2 csg set at 3357' cw 150 sk cmt.

5 1/2 csg PBTD 3310' with perf. (3064-3072)

Set 5 1/2 wood plug at 3000' -poured 10' sd -dumped 4 sk cmt W/dump bailer. (3000-2950)

Cutoff and recovered 2245' of 5 1/2 csg.

Filled 8 5/8 csg W/mud to 365'- set rock & sand bridge (365'-350')

Filled with readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 8/13/74

INV. NO. 9709-W