

15-051-03759-0000

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

OCT 24 1960

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

File No. _____ County: Ellis
Location: NE SE SW Sec. 19 Twp. 11 Rge. 17 (E) (W) _____
Name of Field: _____ Total Depth: 3677

I have this date completed supervision of plugging of:

Lease Name: Peavy Well No. D-3

Operator's Full Name: Champlin Oil & Refg Co

Complete Address: Box 308 Ellinwood, Kans

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 17 Month 10 Year 60

The above well was plugged as follows:

8 5/8" 263' circulated with cement - 5 1/2" 3676' with 100 sax cement.

PB 3637' - Perf 3594'.

Filled with sand to 3580', set 4 sax cement with dump bailer, pulled

2987' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550',

(33 sax Gel) displaced 20 sax cement through 5 1/2" at 550', heavy mud to

240', displaced 20 sax cement through 5 1/2" at 240', heavy mud to 35', set

bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: Jewel M. Ogden
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED
DATE 10/26/60
INV. NO. 2094-W