

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

STATE CORPORATION COMMISSION
SEP 23 1964
09-23-64
CONSERVATION DIVISION

Operator's Full Name Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Lease Name Hadley Well No. D-6

Location SW NE NW Sec. 20 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3503

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith & Halliburton Co.

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 1PM Day 21 Month 9 Year 64

The Above well was plugged as follows:

8 5/8" 1142' circulated with cement - 5 1/2" 3503' with 100 sax cement - PB
5435' - perf 5425'

Pumped 100 sax xement in bottom - squeezed - top cement at 3140'
Pulled 2719' 5 1/2" to 1000' - circulated hole with heavy gel mud through
5 1/2" at 1000' - pulled pipe to 470' - displaced 20 sax cement through
5 1/2" at 470' - heavy mud to 200' and displaced 20 sax cement through
5 1/2" - heavy mud to 30' - cement to bottom cellar.

Mudding and Cementing by Halliburton Co. 500# pump pressure.

I hereby certify that the above well was plugged as herein stated.

DATE 9/23/64
INV. NO: 9854-u

Signed: Leson Patey
Well Plugging Supervisor