

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1972
CONSERVATION DIVISION
Wichita, Kansas
04-27-72

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Hadley "D" Well No. 3

Location C N/2 NE NW Sec. 20 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3696'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 2:30 P Day 24 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3696' 8 5/8 csg set at 1123' cwc: 450 sk. Cmt. Mat. "Halco-Light"

4 1/2 csg set at 3605' cw 200 sk cmt.

4 1/2 csg PBTID 3605' and perf. (3427-3455)

Dakato squeezed and circ to surface with cmt.

Ram 104 jts tbg set at 3175' -pumped 25 sk gel & water W/100 lbs hulls, -displaced

20 sk cmt. Pulled 90 jts tbg set at 420' -circ 95 sk cmt to surface. Pulled

remaining 14 jts tbg and capped 4 1/2 csg W/5 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Lee L. Massey
Well Plugging Supervisor

INVOICED

DATE 5-3-72

INV. NO. 5647-U