

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1978
03-22-78
CONSERVATION DIVISION
Wichita, Kansas
(for this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051-02239-0000

Operator's Full Name Patton Oil Company
Complete Address Englewood, Colorado 80110
Greenwood Plaza No.-5660 S. Syracuse Circle, Suite 200,

Lease Name Hadley Well No. D-7

Location NE NW NW Sec. 20 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3555'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour 1 P Day 20 Month 3 Year 1978

The above well was plugged as follows:

Total Depth 3555' 8 5/8 csg set 1195' cwc 525 sk.

5 1/2 csg set 3545' cw 100 sk cem.

5 1/2 csg PBSD 3535' with Perf. (3500'-2926')

Filled 5 1/2 csg W/sd (3535'-2900') dumped 4 sk cem W/dump bailer. (2900'-2870')

Cutoff & recovered 2511' of 5 1/2 csg.

Set rock & sand bridge at 350' -filled to surface with readymix cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-23-78

INV. NO. 6977-4

Signed: Leo Massey
Well Plugging Supervisor