

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pattco, Inc.

Complete Address 322 70 West Bldg., -70 W. 6th Ave. Denver, Colo. 80204

Lease Name Hadley "D" Well No. 8

Location SW NE NW Sec. 20 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3452

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Glenn & Smith Casing Pulling

Address 204 E. 6th Ellinwood, Kansas License No. 396

Operation Completed: Hour 12N Day 6 Month 11 Year 1969

The above well was plugged as follows:

Total Depth 3452' 8 5/8 csg set at 216' cwc.

5 1/2 csg set at 3450' cw 100 sk cmt.

5 1/2 csg perf. 3431'

Filled 5 1/2 csg W/sd (3400-3452) Dumped 5 sk cmt W/dump bailer (3360-3400)

Cutoff and recovered 639' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls and 100 sk 50-50 poz cmt W/6% gel.

Max. pres. 1000 lbs. SI pres. 700 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Murray
Well Plugging Supervisor

DATE 11/10/69

INV. NO. 804-W