

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SW SW

SEC. 20 TWP. 11 RGE. 17 *w*

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Hadley A *ANBrc*

Operator Walters Drg Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3510 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 171' circulated with cement - 5 1/2" at 3509' with

100 sax cement behind - perforated at 3500'.

Filled with sand to 3480', set 4 sax cement with dump bailer,

pulled 2770' 5 1/2" - pumped hole fill mud (30 sax Gel), pumped

cementing plug to 260', followed by 80 sax cement - cement 260'

to 0'.

Mudding and cementing by Globe Cementing Co.

STATE CORPORATION COMMISSION

JUL 31 1956
07-31-56
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 7-26-56

PLUGGING
FILE SEC. 20 T. 11 R. 17 W
BOOK PAGE 85 LINE 31