

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1973
08-21-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas 67202

Lease Name Hadley "C" Well No. 1

Location NW SW NE Sec. 20 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3408'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12 M Day 17 Month 8 Year 1973

The above well was plugged as follows:

Total Depth 3408' 8 5/8 csg set at 162' cwc 125 sx.

5 1/2 csg set at 3404' cw 75 sx cmt.

~~5 1/2 csg set at 3404' cw 75 sx cmt. (REMOVED)~~

5 1/2 csg squeezed at 1065' with 2300 sx cement. No pipe recovered.

Pumped down 5 1/2 csg W/20 sk cmt--4 sk hulls--30 sk gel & water--released 5 1/2 plug

& pumped 55 sk cmt. Max PP 800 lbs. SIP 500 lbs.

Pumped 10 sk cmt down annulus.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/22/73
INV. NO. 4999-W

Signed: Leo F. Massey
Well Plugging Supervisor