

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-051-05505-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Patton Oil Company

Complete Address 672 W. 4th St. Herington, Ks. 67544

Lease Name Hodley Well No. B-2

Location NW NE SW Sec. 20 Twp. 11 Rge. 17 (East) (West) (West)

County Ellis Total Depth 3425'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. Inc.

Address Box 32 W. Wichita, Russell, Ks. 67665 License No. _____

Operation Completed: Hour: 10:45 AM Day: 14 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 162' SP. cas. w/150 sacks cement. 5 1/2" casing set at 3406' w/125 sacks cement.
Open hole 19'. Squeezed at 300' w/300 sacks cement. No. pipe pulled.
Ordered 165 sacks ⁵⁰ 50% pozz mix - 4% Gel - 3% Cal. Cl., 20 sacks Gel, 5 sacks hulls, + 8 5/8"
plug. Pumped into 5 1/2" casing, 4 hulls, 15 sacks Gel, 70 sacks cement, 5 sacks Gel,
1 sack hulls, released plug + followed w/20 sacks cement. Pumped 25 sacks cement
into 8 5/8" SP.

Maximum pressure 200 pounds

Amount of Surface Casing: 162' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Marion Schmidt
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

200
09-27-82

STATE RECEIVED
1 SEP 27 1982
CONSERVATION DIVISION
Wichita, Kansas
NOVOICED
10-5-82
V. NO. 1307-W