

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 24 1960  
10-24-60  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis  
Location: SE SW SE Sec. 20 Twp. 11 Rge. 17 (E) (W) \_\_\_\_\_  
Name of Field: \_\_\_\_\_ Total Depth: 3686

I have this date completed supervision of plugging of:

Lease Name: Hadley Well No. E-2

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Plugging Contractor: Ace Pipe Pulling Co

Address: Great Bend, Kans License No. 2

Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 4:30PM Day 18 Month 10 Year 60

The above well was plugged as follows:

8 5/8" 1333' circulated with cement - 5 1/2" 3686' with 100 sax cement - PB  
3654' - perforated 3402' - perforations squeezed off - P.B to 3350', set  
sand and 4 sax cement with dump bailer - pulled 2720' 5 1/2" to 550',  
circulated hole with heavy mud through 5 1/2" at 550', displaced 20 sax  
cement through 5 1/2" at 550', heavy mud to 250', displaced 20 sax cement  
through 5 1/2" at 250', heavy mud to 35', set rock and 10 sax cement to 0'.  
Mudding and cementing by Sun Cementing Co.

Signed: Leon Petty  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

INVOICED  
DATE 10/24/60  
INV. NO. 2129-u