



15-051-03774-0000

GEORGE DOCKING Governor  
 MARION BEATTY Chairman  
 HARRY G. WILES Commissioner  
 RICHARD C. BYRD Commissioner  
 RAYMOND B. HARVEY Secretary  
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS  
 JEWEL M. OGDEN, Director

STATE CORP. COM.  
 MAR 19 1959  
 CONSERVATION DIVISION  
 WICHITA, KANSAS  
 VED

Jewel M. Ogden, Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

I have this date 3-15-59, 19    , authorized the following plugging operation:

Operator's Full Name: Murfin Drg Co

Complete Address: 617 Union Center Wichita, Kans

Lease Name: Peavey Well No. 7

Location: NE NW NE Sec. 19 Twp. 11 Rge. 17 (E) (W)

County: Ellis Total Depth: 3540

Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Operator was instructed to plug well as follows:

Circulate hole with heavy mud, set plug at 600', displace 20 sax cement  
 through drill pipe, heavy mud to 180', set plug and 15 sax cement, mud to  
 40', set plug, hulls and 10 sax cement.

Very truly yours,

Signed: *Leon Betty*  
 Conservation Division Agent