

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999

Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

12/03/08

Operator: License # 33476
Name: FIML Natural Resources, LLC
Address: 410 17th Street Ste. 900
City/State/Zip: Denver, CO. 80202
Purchaser: NCRA
Operator Contact Person: Cassandra Parks
Phone: (303) 893-5090
Contractor: Name: Murfin Drilling Company
License: 30606

CONFIDENTIAL

DEC 03 2008

Wellsite Geologist: _____
Designate Type of Completion: KCC
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____

Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>9/23/2008</u>	<u>9/30/2008</u>	<u>11/6/2008</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 171-20709-00-00
County: Scott
NE SW NW Sec. 9 Twp. 19 S. R. 31 East West
1650 feet from S (N) (circle one) Line of Section
990 feet from E (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE (NW) SW
Lease Name: Pfeifer-Ball Well #: 5A-9-1931

Field Name: Grigston Southwest
Producing Formation: Mississippi
Elevation: Ground: 2971' Kelly Bushing: 2893'
Total Depth: 4836 Plug Back Total Depth: 4797'
Amount of Surface Pipe Set and Cemented at 8 jts @ 368' Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set 2985' DV tool _____ Feet
If Alternate II completion, cement circulated from 2985'
feet depth to surface w/ 480 _____ sx cmt.

Drilling Fluid Management Plan AM IJW 22409
(Data must be collected from the Reserve Pit)
Chloride content 6500 ppm Fluid volume 1200 bbls
Dewatering method used _____

Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.


All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: Regulatory Specialist Date: 12/3/2008
Subscribed and sworn to before me this 3 day of December
2008.
Notary Public: Elaine Winick
Date Commission Expires: 5/5/2009

KCC Office Use ONLY

Letter of Confidentiality Received
 Wireline Log Received
 Geologist Report Received
 IUC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 05 2008



CONSERVATION DIVISION
WICHITA, KS

5A-9-1931

Operator Name: FIML Natural Resources, LLC Lease Name: Pfeifer-Ball Well #: 5A-9-1931
 Sec. 9 Twp. 19 S. R. 31 East West County: Scott

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Array Compensated Resistivity; Spectral Density/Dual Spaced Neutron; Microlog	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table border="0"> <tr> <td style="width:60%">Name</td> <td style="width:20%">Top</td> <td style="width:20%">Datum</td> </tr> <tr> <td>Topkea</td> <td>3663'</td> <td>-680</td> </tr> <tr> <td>Heebnier</td> <td>3908'</td> <td>-925</td> </tr> <tr> <td>Lansing</td> <td>3949'</td> <td>-966</td> </tr> <tr> <td>Base of Kansas City</td> <td>4335'</td> <td>-1352</td> </tr> <tr> <td>Cherokee</td> <td>4510'</td> <td>-1527</td> </tr> <tr> <td>Mississippi Spergen</td> <td>4607'</td> <td>-1624</td> </tr> </table>	Name	Top	Datum	Topkea	3663'	-680	Heebnier	3908'	-925	Lansing	3949'	-966	Base of Kansas City	4335'	-1352	Cherokee	4510'	-1527	Mississippi Spergen	4607'	-1624
Name	Top	Datum																				
Topkea	3663'	-680																				
Heebnier	3908'	-925																				
Lansing	3949'	-966																				
Base of Kansas City	4335'	-1352																				
Cherokee	4510'	-1527																				
Mississippi Spergen	4607'	-1624																				

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24.0#	368'	"A" common	255	2% gel & 3% CaCl ₂
Production	7-7/8"	5-1/2"	15.5#	4822'	ASC	345	2% gel 10% salt
			DV tool	2985	Lite	480	0.25 pps flo & 5 pps gil

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone	Mouse & rat hole	Lite	25	0.25 pps flocele & 5 pps gilsonite


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
1	4609-4616'	Acidize with 1000 gal 15% MCA	4609-4616'

TUBING RECORD		Size	Set At	Packer At	Liner Run	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
		2-3/8"	4780'				
Date of First, Resumerd Production, SWD or Enhr. 11/18/2008			Producing Method				
			<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)				
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity		
	36		108				

Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____





24 S. Lincoln Street
 P.O. Box 31
 Russell, KS 67665-2906

Voice: (785) 483-3887
 Fax: (785) 483-5566

RECEIVED
 OCT 06 2008

INVOICE

Invoice Number: 116366
 Invoice Date: Oct 1, 2008
 Page: 1

Bill To:
 FIML Natural Resources LLC
 410 17th St., #900
 Denver, CO 80202

CONFIDENTIAL
 DEC 03 2008
 KCC

Customer ID	Well Name# or Customer P.O.	Payment Terms	
FIML	PfieferBall#5A9-1931	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS1	Oakley	Oct 1, 2008	10/31/08

Quantity	Item	Description	Unit Price	Amount
505.00	MAT	Lightweight Class A	14.05	7,095.25
125.00	MAT	Flo Seal	2.50	312.50
2,525.00	MAT	Gilsonite	0.89	2,247.25
561.00	SER	Handling	2.40	1,346.40
60.00	SER	Mileage 561 sx @ .10 per sk per mi	56.10	3,366.00
1.00	SER	Production String - Top Stage	1,185.00	1,185.00

RECEIVED
 KANSAS CORPORATION COMMISSION
 DEC 05 2008
 CONSERVATION DIVISION
 WICHITA, KS

D08139
8200-118
Adam D. Blum
2nd stage

ALL PRICES ARE NET, PAYABLE
 30 DAYS FOLLOWING DATE OF
 INVOICE. 1 1/2% CHARGED
 THEREAFTER. IF ACCOUNT IS
 CURRENT, TAKE DISCOUNT OF

\$ 1555.24

ONLY IF PAID ON OR BEFORE

Oct 31, 2008

Subtotal	15,552.40
Sales Tax	608.27
Total Invoice Amount	16,160.67
Payment/Credit Applied	
TOTAL	16,160.67

-1555.24
14,605.43

ALLIED CEMENTING CO., LLC. 32078

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley KS

DATE <i>10/08</i>	SEC <i>9</i>	TWP <i>19</i>	RANGE <i>31</i>	CALLED OUT	ON LOCATION	JOB START <i>1:30 pm</i>	JOB FINISH <i>2:30 pm</i>
LEASE <i>Ball</i>	WELL # <i>5A-9-194</i>		LOCATION <i>South City Eg 5 4 1/2 E 5</i>		COUNTY <i>Worth</i>	STATE <i>KS</i>	
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR *Man Av 21*

TYPE OF JOB *Production top Stage*

HOLE SIZE _____ T.D. _____

CASING SIZE *5 1/2* DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL *DV Tool* DEPTH *2987'*

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT *7 3/4 BBL*

OWNER *Senie*

CEMENT

AMOUNT ORDERED *505 SK 60/40 87 bagel*

5 lb Gilsonite, 1/4 lb Flo Seal

EQUIPMENT

PUMP TRUCK CEMENTER *Alan*

422 HELPER *Wayne*

BULK TRUCK

344 DRIVER *John*

BULK TRUCK

398 DRIVER *Jerry*

COMMON	<u>CONFIDENTIAL</u>		
POZMIX	<i>DEC 05 2008</i>		
GEL			
CHLORIDE	<i>KCC</i>		
ASC			
<i>505 SKs Lite</i>	<i>14.09</i>	<i>7095.25</i>	
<i>Flo Seal 125 lb</i>	<i>2.50</i>	<i>312.00</i>	
<i>Gilsonite 2525 lb</i>	<i>.89</i>	<i>2247.25</i>	
HANDLING <i>561 SKs</i>	<i>2.40</i>	<i>1346.40</i>	
MILEAGE <i>10.4 SK/mile</i>		<i>336.60</i>	
		TOTAL	<i>14367.40</i>

REMARKS:

*Mix 15 SKs Rathole, 10 SKs Monor Hoop
max 480 SKs down 5 1/2. Clean track &
lines. Displacement w/ 7 3/4 BBL water.
1300 lb LIFT Pressure Load Plug @
lbs. Tool Held.*

Cement did Circulate

*Thank you Alan Wayne
Jerry, John*

CHARGE TO: *FIML*

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB *2987' 33"*

PUMP TRUCK CHARGE *1185.00*

EXTRA FOOTAGE @ _____

MILEAGE *60 miles* @ *N/C*

MANIFOLD @ _____

RECEIVED
KANSAS CORPORATION COMMISSION @ _____

DEC 05 2008

TOTAL *1185.00*

CONSERVATION DIVISION
WICHITA, KS
PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME *Gary Doka*

SIGNATURE *[Signature]*

TOTAL _____

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906

Voice: (785) 483-3887
Fax: (785) 483-5566

RECEIVED
OCT 06 2008

INVOICE

Invoice Number: 116365
Invoice Date: Oct 1, 2008
Page: 1

Bill To:
FIML Natural Resources LLC
410 17th St., #900
Denver, CO 80202

CONFIDENTIAL
DEC 03 2008
KCC

Customer ID	Well Name# or Customer P.O.	Payment Terms	
FIML	PfeiferBall#5A9-1931	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS1	Oakley	Oct 1, 2008	10/31/08

Quantity	Item	Description	Unit Price	Amount
6.00	MAT	Gel	20.80	124.80
345.00	MAT	ASC Class A	18.60	6,417.00
34.00	MAT	Salt	23.95	814.30
500.00	MAT	WFR-2	1.27	635.00
424.00	SER	Handling	2.40	1,017.60
60.00	SER	Mileage 424 sx @ .10 per sk per mi	42.40	2,544.00
1.00	SER	Production String - Bottom Stage	2,185.00	2,185.00
60.00	SER	Mileage Pump Truck	7.00	420.00
1.00	SER	Manifold Head Rental	113.00	113.00
1.00	EQP	Lock Collar	29.00	29.00
1.00	EQP	D V Tool	4,500.00	4,500.00
1.00	EQP	Non Fill Float Shoe	529.00	529.00
1.00	EQP	Sure Seal Float Collar	372.00	372.00
25.00	EQP	Centralizers	57.00	1,425.00
2.00	EQP	Baskets	186.00	372.00

D08139
8200-118
Adam Q. Blum
1st stage

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 05 2008
CONSERVATION DIVISION
WICHITA, KS

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF

\$ 2149.77

ONLY IF PAID ON OR BEFORE

Oct 31, 2008

Subtotal	21,497.70
Sales Tax	958.74
Total Invoice Amount	22,456.44
Payment/Credit Applied	
TOTAL	22,456.44

- 2149.77
20,306.67

ALLIED CEMENTING CO., LLC. 32077

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

CONFIDENTIAL

SERVICE POINT: Oakley, KS

DEC 03 2008

DATE <u>10/1/08</u>	SEC <u>9</u>	TWP <u>19</u>	RANGE <u>31</u>	CABLED OUT <u>KCC</u>	ON LOCATION <u>3:00 pm</u>	JOB START <u>8:00 am</u>	JOB FINISH <u>9:50 am</u>
PF eifer <u>Bell</u> LEASE	WELL # <u>5A-9-1931</u>		LOCATION <u>SW 1/4 Sec 8E 4 1/2 E 6 S Int</u>		COUNTY <u>Scott</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR Murfin 21
 TYPE OF JOB Production Bottom Stage
 HOLE SIZE 7 7/8 T.D. 4822
 CASING SIZE 5 1/2 / 15 1/2 in DEPTH
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL D.V. DEPTH 2987 3/4 FT
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT 18.08 FT
 CEMENT LEFT IN CSG. 18.08 FT
 PERFS.
 DISPLACEMENT 45 BBL Water, 69 1/2 BBL Mud
 EQUIPMENT 114 1/2 TOTAL BBL

OWNER Samy
 CEMENT
 AMOUNT ORDERED 345 SKS ASC 1090
Salt 270 gel
500 gal WFR II
 COMMON ~~ASC~~ @ _____
 POZMIX @ _____
 GEL 6 @ 20.00 124.00
 CHLORIDE @ _____
 ASC 345 @ 18.60 6417.00
34 SKS Salt @ 23.25 814.30
500 Gal WFR II @ 1.20 635.00
 HANDLING 424 SKS @ 2.40 1017.60
 MILEAGE 109 SK/mile @ _____ 2544.00
 TOTAL 11552.90

PUMP TRUCK CEMENTER Alan
 # 422 HELPER Wayne
 BULK TRUCK
 # 399 DRIVER Jerry
 BULK TRUCK
 # 394 DRIVER John

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 05 2008
CONSERVATION DIVISION
WICHITA, KS

REMARKS:

mix 300 WFR II, mix 345 SKS ASC
1090 Salt 270 gel. Wash Truck on Lines
Dis place plug w/ 45 BBL Water, 69 1/2 BBL
Mud. Land Plug @ 1800 lb w/ 1100 lb LIFT
Pressure & Drop DV opening tool, open
DV tool w 900 lb pressure Circulate
For 4 hrs.
Thank You
Alan, Wayne, Jerry, John

SERVICE
 DEPTH OF JOB 41 FT 4822
 PUMP TRUCK CHARGE 2185.00
 EXTRA FOOTAGE @ _____
 MILEAGE 60 @ 7.00 420.00
 MANIFOLD Head & Manifold @ _____ 113.00
 TOTAL 2718.00

CHARGE TO: FIML
 STREET _____
 CITY _____ STATE _____ ZIP _____

5 1/2"

To Allied Cementing Co., LLC.
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT
 Lock collar 29.00
 DV TOOL @ 4500.00
 Float shoe Non Fill @ 529.00
 Float collar - Shim Seal @ 372.00
 Centralizers - 25 @ 57.00 1425.00
 Baskets - 2 @ 186.00 372.00
 ↓
1 Blue
 TOTAL 7227.00

PRINTED NAME Gary Deke
 SIGNATURE [Signature]

SALES TAX (If Any) _____
 TOTAL CHARGES _____
 DISCOUNT _____ IF PAID IN 30 DAYS



24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906

Voice: (785) 483-3887
Fax: (785) 483-5566

RECEIVED
SEP 29 2008

INVOICE

Invoice Number: 116251
Invoice Date: Sep 23, 2008
Page: 1

Bill To:
FIML Natural Resources LLC
410 17th St., #900
Denver, CO 80202

CONFIDENTIAL

DEC 03 2008

KCC

Customer ID	Well Name# or Customer P.O.	Payment Terms	
FIML	PfeiferBall5A-9-1931	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS1	Oakley	Sep 23, 2008	10/23/08

Quantity	Item	Description	Unit Price	Amount
255.00	MAT	Class A Common	15.45	3,939.75
5.00	MAT	Gel	20.80	104.00
9.00	MAT	Chloride	58.20	523.80
269.00	SER	Handling	2.40	645.60
60.00	SER	Mileage 269 sx @ .10 per sk per mi	26.90	1,614.00
1.00	SER	Surface	1,018.00	1,018.00
70.00	SER	Extra Footage	0.85	59.50
60.00	SER	Mileage Pump Truck	7.00	420.00
1.00	SER	Manifold Head Rental	113.00	113.00
1.00	EQP	AFU Insert	377.00	377.00
3.00	EQP	Centralizers	62.00	186.00
1.00	EQP	Rubber Plug	113.00	113.00

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 05 2008
CONSERVATION DIVISION
WICHITA, KS

8100-145
Adam D. B...
D08139

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF

\$ 911.36

ONLY IF PAID ON OR BEFORE

Oct 23, 2008

Subtotal	9,113.65
Sales Tax	330.34
Total Invoice Amount	9,443.99
Payment/Credit Applied	
TOTAL	9,443.99

-911.36
8532.63

ALLIED CEMENTING CO., LLC. 043825

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665.

SERVICE POINT:
Oakley

DATE <u>9-23-08</u>	SEC. <u>9</u>	TWP. <u>19s</u>	RANGE <u>31w</u>	CALLED OUT	ON LOCATION <u>9:00pm</u>	JOB START <u>2:45Am</u>	JOB FINISH <u>3:45Am</u>
LEASE <u>Pfeifer Ball</u>	WELL # <u>5A-9-1931</u>	LOCATION <u>Scott City 8 E 4 1/2 S</u>			COUNTY <u>Scott</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)				<u>E S into</u>			

CONTRACTOR Murfin Drilling Rig 21

TYPE OF JOB Sur Face

HOLE SIZE 12 1/2 T.D. 372'

CASING SIZE 8 5/8 DEPTH 370.16'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT 44.65'

CEMENT LEFT IN CSG. 44.65'

PERFS. _____

DISPLACEMENT 20.23 BBL

OWNER same

CEMENT

AMOUNT ORDERED 255 sks com
3% ca 2% gel

COMMON <u>255 sks</u>	@ <u>15.45</u>	<u>3939.75</u>
POZMIX _____	@ _____	_____
GEL <u>5 sks</u>	@ <u>20.80</u>	<u>104.00</u>
CHLORIDE <u>9 sks</u>	@ <u>58.20</u>	<u>523.80</u>
ASC _____	@ _____	_____

EQUIPMENT

PUMP TRUCK CEMENTER Andrew

423-281 HELPER Alvin

BULK TRUCK

218 DRIVER John

BULK TRUCK

_____ DRIVER _____

RECEIVED
KANSAS CORPORATION COMMISSION

CONFIDENTIAL

DEC 05 2008

CONSERVATION DIVISION
WICHITA, KS

KCC

HANDLING <u>269 sks</u>	@ <u>2.40</u>	<u>645.60</u>
MILEAGE <u>107 sk/mile</u>		<u>1614.00</u>
		TOTAL <u>6827.15</u>

REMARKS:

Cement did circulate

thank you

SERVICE

DEPTH OF JOB <u>370.16'</u>		
PUMP TRUCK CHARGE		<u>1018.00</u>
EXTRA FOOTAGE <u>70'</u>	@ <u>.85</u>	<u>59.50</u>
MILEAGE <u>60 miles</u>	@ <u>7.00</u>	<u>420.00</u>
MANIFOLD <u>head rental</u>	@	<u>113.00</u>
		TOTAL <u>1610.50</u>

PLUG & FLOAT EQUIPMENT

8 5/8

<u>1 AFU INSERT</u>	@	<u>372.00</u>
<u>3 Centralizers</u>	@ <u>62.00</u>	<u>186.00</u>
<u>1 Rubber plug</u>	@	<u>113.00</u>
		TOTAL <u>671.00</u>

CHARGE TO: FIML

STREET _____

CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME W Gary Duke

SIGNATURE W Gary Duke 620 640 5918

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS