



15-051-21054-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 12 1975
05-12-1975
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Reiter of Murfin Drlg. has this
date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee:

Operator's full Name: Don E. Pratt

Complete Address: Box 370, Hays, Kansas 67601

Lease Name: Staab Well No. 3

Location: NW SW SE Sec. 8⁸ Twp. 13 Rge. (E)(W) 17

County: Ellis Total Depth 3627' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Reiter was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe. Heavy mud to 125' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent