

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Richard Schmidtberger of Ranger Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: A. W. Leikam Oil Operations

Complete Address: 505 Riley St., Hays, Ks. 67601

Lease Name: Leikam Well No. #1

Location: S/2 NE NW Sec. 8 Twp. 13 Rge. 17 (E) (W)

County: Ellis Total Depth: 3650'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Richard Schmidtberger was instructed to plug the well as follows:

8 5/8"-201' s.p. cuc. w/130 sacks 60/40 posmix-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug-@ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/70 sacks cement

Circulated with 10 sacks cement in rat hole.

Very truly yours

[Signature]
Conservation Division Agent

RECEIVED

DEC-7 1981

12-07-1981
CONSERVATION DIVISION
Wichita, Kansas