

15-051-22012-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION CP-4
Rev. 12-15-80

NOV 08 1982
11-08-1982
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Ellis SEC. 35 TWP. 13s RGE. 16w E/W
Location as in quarters or footage from lines:
70' W of C SW SE NW

Lease Owner K & E Drilling Inc.

Lease Name Brungardt "B" #1 Well No. _____

Office Address 2008 11th St., Great Bend, Ks. 67530

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 10/26/82

Plugging completed 10/28/82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation _____ Depth to top _____ bottom T.D. 3520'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	318	none
				4 1/2"	3464	2603'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Run sand to 3150 & 4 sacks cement, shot casing at 2606' pulled 63
joints. Plugged well with 25 sacks cement, 4 hulls, 15 gel, 70 cement
5 gel, 1 hull, 8 5/8 plug, 70 cement.

Plugging completed

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 82



My Commission expires:

Irene Hoover
Notary Public.

15-051-22012-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	K & E Petroleum, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Brungardt "B" #1
LOCATION:	70' West of SW SE NW, Section 35-13S-16W Ellis County, Kansas
SPUD DATE:	07-19-80
COMPLETION DATE:	07-28-80

0	1036	Sand & Shale
1036	1078	Anhydrite
1078	1248	Sand & Shale
1248	3520	Shale & Lime
	3520	Rotary Total Depth

Spud hole at 10:30 p.m. 07-19-80. Drilled 322' of a 12-1/4" hole. Ran 8 joints of 8-5/8" - 20# casing (tally 312.44). Set at 318.94'. Cemented with 190 sx. of common, 2% gel, 3% c.c. Cement did circulate. Plug was down at 6:45 a.m. 07-20-80.

T.D. 3820', L.T.D. 3824'. Ran 84 joints of 4-1/2" - 9-1/2# casing (tally 3474.05). Set at 3478'. Cemented with 150 sx. of 50/50 posmix, salt saturated. Job completed 8:45 a.m. 07-28-80.

SAMPLE TOPS:

Anhydrite 1036'
B/Anhydrite 1078'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BRUNGARDT "B" #1, 70' West of SW SE NW, Section 35-13S-16W, Ellis County, Kansas.

ABERCROMBIE DRILLING, INC.

Jack L. Partridge
BY _____
Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 5th day of August, 1980.

Sherrie L. Brooks

Sherrie L. Brooks, Notary Public



RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1982
08-17-1982
CONSERVATION DIVISION
Wichita, Kansas