


15-051-00982-1000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County Sec. 35 Twp 13S Rge. 16 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE  
Lease Owner Texas Company, S. A. Yarnell & Pyramid Drilling Company  
Lease Name Kippes Well No. 1  
Office Address 300 Schweiter Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-21-50 19  
Application for plugging filed 2-20-50 19  
Application for plugging approved 2-20-50 19  
Plugging commenced 2-21-50 19  
Plugging completed 2-21-50 19  
Reason for abandonment of well or producing formation  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation None Depth to top Bottom Total Depth of Well 3548 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	245			None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Hole was pumped full of heavy mud to bottom of surface pipe (245').  
Plug set at 245' and cemented through drill pipe with 15 sacks cement.  
Plug set 10' below bottom of Cellar and cemented with 10 sacks cement.

03-16-1950

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to Pyramid Drilling Company, Inc.  
Address 300 Schweiter Building  
Wichita, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Pyramid Drilling Co. Inc.  
By J. J. Ferrier Pres.  
300 Schweiter Bldg Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March 1950  
Notary Public.



TEXAS CO., S. A. YARNELL & PYRAMID DRILLING CO., INC.  
DRILLING LOG

Lease: Kippes  
Well No.: 1

County: Ellis  
Location: NW SE  
Section: 35-133-16W

Commenced: February 8, 1950  
Completed: February 21, 1950  
Surface Pipe: 245' 8-5/8"

0 - 40	Clay	2505 - 2615	Lime & Shale
40 - 218	Hard Sand & Shale	2615 - 2730	Shale & Lime
218 - 248	Shale	2730 - 2845	Shale & Lime
248 - 500	Shale & Shells	2845 - 2856	Lime (Broken)
500 - 665	Sand	2856 - 2930	Lime (Broken)
665 - 850	Shale & Red Bed	2930 - 2975	Lime (Broken)
850 - 1030	Red Bed	2975 - 3038	Lime
1030 - 1067	Anhydrite	3038 - 3106	Lime
1067 - 1140	Shale	3106 - 3155	Lime
1140 - 1375	Shale & Shells	3155 - 3171	Lime & Shale
1375 - 1685	Shale & Shells	3171 - 3206	Lime (F. C.)
1685 - 1840	Shale & Shells	3206 - 3226	Lime
1840 - 1975	Lime & Shale	3226 - 3267	Lime (Cherty)
1975 - 2070	Lime (Broken)	3267 - 3358	Lime
2070 - 2130	Lime (Broken)	3358 - 3412	Lime & Shale
2130 - 2190	Lime	3412 - 3484	Lime
2190 - 2330	Lime	3484 - 3520	Lime & Chert
2330 - 2425	Shale & Shells	3520 - 3548	Cherty Lime & Shale
2425 - 2505	Lime & Shale	3510	Top Arbuckle

I, T. L. Ferrier, President of the Pyramid Drilling Company, Inc., hereby certify that this is a true and correct copy of the above log to the best of my knowledge and belief.

T. L. Ferrier

04-20-1950

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 3rd day of March, 1950.

Almeda J. Farnacht

My commission expires May 25, 1952

