

14

WELL PLUGGING RECORD

Information Completely
to Attached Affidavit
to Deliver Report to:
Conservation Division
State Corporation Commission
931 No. Broadway
Wichita, Kansas

Ellis ~~Wagoner~~ County, Sec. 35 Twp. 13S Rgo. 16E (E) (W)

Location as "NE/CNW/SE" or fraction from lines. ~~NE NE NE~~

Lease Owner Don E. Pratt

Lease Name Brungardt Well No. 1

Office Address Box 656 Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 19

Application for plugging filed January 23, 1963 19

Application for plugging approved January 24, 1963 19


Plugging commenced January 26, 1963 19

Plugging completed January 30, 1963 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3473 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	175	none
				5 1/2	none	2822

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved on and set up unit. Measured T.D. and banded to 3800'. Dumped 5 sx. cement.

Cleaned out cellar, rigged up jacks and worked pipe. Shot @ 2807'.

Worked and started pipe. Pulled 30 jts.

Pulled rest of pipe.

Circulated mud @ 500' and dumped 20 sx. cement. Pulled to 180' and dumped 20 sx. cement. Pulled rest of pipe and capped well with 10 sx. cement.

RECEIVED
FEB 14 1963
02-14-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J O Forbes

Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 31st day of January, 1963

Carolyn A. Green

Notary Public.

My commission expires July 23, 1966

DRILLERS LOG

CASING RECORD:	COMPANY:	Don E. Pratt	DESCRIPTION:	NW NW NE
8 5/8" @ 177'	CONTRACTOR:	Red Tiger Drilling Co.		35-135-10W
w/125 xx cement	COMMENCED:	July 20, 1962		Ellis Co.,
5 1/2" @ 3471'	COMPLETED:	July 29, 1962	ELEVATION:	Kansas
w/125 xx cement				
TOTAL DEPTH:				3473'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Sand	0	165	
Shale	165	540	
Sand	540	670	
Shale & Redbed	670	990	
Shale	990	1021	
Anhydrite	1021	1420	
Shale	1420	1800	
Lime & shale	1800	2170	
Lime	2170	2530	
Lime & shale	2530	2935	
Lime	2935	3473	

JAN 29 1963
 01-29-1963

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine Head

Maxine Head

Subscribed and sworn to before me this 30th day of July, 1962.

Jean Hollar

Notary Public

My Commission Expires:

5-22-80