


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 35 Twp. 13S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines NW SE NE

Lease Owner Schreiner Petroleum

Lease Name Brungardt Well No. 1

Office Address 207 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 9-24-68 19 68

Application for plugging filed 10-12 19 68

Application for plugging approved 10-12 19 68

Plugging commenced 10-12 10/12/ 19 68

Plugging completed 10/22 19 68

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Depth to top Bottom Total Depth of Well 3491 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	TO	SIZE	PUT IN	PULLED OUT
Shale		247	8 5/8	247	none

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1968
CONSERVATION DIVISION
Wichita, Kansas
11-06-1968

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back to 3100' with sand, dumped 5 sacks cement, pumped 10 sacks mud, & 130 sacks cement to top.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Lynch Casing Pulling co
Address Rt 4, Great Bend, Kans

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R.J. Schreiner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.J. Schreiner
207 Petro Bldg Wichita, Kans (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of November, 19 68

My commission expires May 31, 1970

Alma A. Neises Notary Public.

September 30, 1968

DRILLERS LOG

Re: #1 Brungardt
NW SE NE Sec. 35-13S-16W
Ellis County, Kansas

COMPANY: Schreiner Petroleum
CONTRACTOR: B & B Drilling, Inc.
TOTAL DEPTH: 3491
COMMENCED: 9-16-68
COMPLETED: 9-24-68

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1968
CONSERVATION DIVISION
Wichita, Kansas
11-06-1968


0	250	Shale
250	540	Shale
540	630	Sand
630	1010	Red Rock & Shale
1010	1070	Anhydrite & Shale
1070	1560	Shale
1560	1895	Shale & Lino
1895	2095	Lino
2095	2235	Lino
2235	2470	Shale & Lino
2470	2698	Lino & Shale
2698	2855	Lino
2855	3010	Lino & Shale
3010	3140	Lino
3140	3205	Lino
3205	3310	Lino
3310	3397	Lino
3397	3404	Base K.C.
3404	3426	Sand
3426	3488	Sand Cong. Arb.
3488	3491	Arbuckle
3491		Total Depth

DST #1

DST #2

DST #3

Set 3490' og 4 1/2" casing w/125 ex.



We certify the above and foregoing to be true and correct copy of the log on the #1 Brungardt, located in Ellis County, Kansas.

Bill D. [Signature] President

Alma A. Heiser Notary Public

Subscribed and sworn to before me this 30th day of September, 1968

MY commission expires May 31, 1970