

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-051-01484-00-00 Form CP-4  
WELL PLUGGING RECORD

Ellis County, Sec. 35 Twp. 13S Rge. 10W (X) (W)

Location as "NE/CNW/SW" or footage from lines SE NE NW

Lease Owner Don Pratt

Lease Name E. Brungardt Well No. 1

Office Address Box 656, Hays, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D & A

Date well completed January 21 1963

Application for plugging filed January 21 1963


Application for plugging approved January 21 1963

Plugging commenced January 21 1963

Plugging completed January 21 1963

Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3481 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	174'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Fill hole with heavy mud to 480'  
plug & 20 sx cement. Fill to 170' w/  
heavy mud. Plug & 20 sx cement. Fill  
to 45' with heavy mud 1/2 sx hulls. Plug  
& 10 sx cement.

RECORDED  
FEB 6 1963  
02-06-1963  
CONSERVATION DIV  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling

Address Box 173--Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.

George A. Angle (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle

580 Fourth National Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of January, 19 63

Notary Public

My commission expires 11-17-66

DRILLERS LOG

Brungardt No. 1

15-051-01484-00-00

CASING RECORD: 8 5/8" @ 1741' w/135 sx cement  
 COMPANY: Don Pratt  
 CONTRACTOR: Red Tiger Drilling Co.  
 COMMENCED: January 14, 1963  
 COMPLETED: January 21, 1963  
 DESCRIPTION: SE NE NE 35-13S-16E  
 Ellis Co., Kansas  
 ELEVATION: 1928 DF  
 1931 RB  
 TOTAL DEPTH: 3481'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale & Shells	0	175	
Shale & Sand	175	540	
Sand	540	730	
Shale & Red Bed	730	1029	
Anhydrite	1029	1072	
Shale	1072	1490	
Shale & Shells	1490	1870	
Shale	1870	2070	
Lime & Shale	2070	2980	
Lime	2980	3481	

I certify that this a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle  
 George A. Angle

Subscribed and sworn to before me this 23rd day of January, 1963.

Wm. L. Hance  
 Notary Public

My Commission Expires:

11-17-66

01-31-1963